



(A Govt. of India Enterprise)
OFFICE OF THE EXECUTIVE ENGINEER (CIVIL),
BSNL CIVIL DIVISION, DOOR SANCHAR BHAWAN, THIRD FLOOR, UNIT-IX,
BHUBANESWAR, PIN- 751022

SHORT NOTICE INVITING QUOTATION

Item rate quotations for the work as mentioned below are invited by the Executive Engineer (Civil), BSNL Civil Division, Bhubaneswar, 3rd floor, Unit-IX, Door Sanchar Bhawan, PIN: - 751022 for and on behalf of the BSNL for the following urgent work from registered Contractor.

1.0 The last date of receipt of application for issue of quotation forms (In prescribed format/ can also be downloaded from BSNL Website (www.odisha.bsnl.co.in) and date of issue of quotation forms will be as follows:

- I) Last date of receipt of application : **25.06.2019 up to 15.00 Hrs.**
- II) Last date of issue of quotation forms : **25.06.2019 up to 15.30 Hrs**

The last date of receipt of quotation is on **26.06.2019** up to **15.00** hours. The quotation will be opened on the same day at **15.30** hours.

Envelope no.1 shall contain the license/registration copy, the copy of **PAN card** and GST registration signed by the applicant therein. Envelope no.2 shall contain the quotation bid/Financial bid. Envelope no.1 and Envelope no.2 shall be put in one covering envelope in top of which the name of work must be mentioned.

Sl. no	Name of Work	Estimated cost (Rs)	Time allowed
1.	Dismantling of fallen roof top poles damaged by very severe cyclone "FANI" at various locations of Bhubaneswar City. NIQ/ 12/2019-20 /BCD/SDE-III/BBSR.	61,200.00	05(Five) days

TERMS AND CONDITIONS

1. The quoted rates shall be inclusive of all taxes i/c GST .
2. Payment will be made after completion the work as per the latest C.P.W.D specifications/as per direction of Engineer-in- Charge.
3. The authority reserves the right to accept/cancel any offer without assigning any reason thereof.
4. The offer shall remain valid for **5(Five) days**.
5. The site of work is available.
6. The work being very urgent nature, the quotationer should start the work immediately after issue of work order in consultation with SDE(C), **BCSD-III**, BBSR. Hence, the quotationer should be prepared for the same
7. For approved make and approved shade/design, EE(C), BSNL Civil Division, BBSR may be contacted.
8. For any disputes arising out of it, if any, the decision of the Superintending Engineer(C), O/o CE(C), BSNL Civil Odisha Zone, Bhubaneswar shall be final and binding.

Sd/-
Executive Engineer(C)
BSNL civil Division
Bhubaneswar

No. NIQ/**12/2019-20**/BCD/SDE-III/BBSR/246

Dated: 20 .06.2019

Copy to:-

1. The C.G.M.T., BSNL Orissa Circle, Bhubaneswar-751001.
2. The GMTD, BSNL Telecom District, Bhubaneswar.
3. The Chief Engineer(C), BSNL Civil Odisha Zone, Bhubaneswar.
4. The Executive Engineer ©, BSNL Civil Division No II, Bhubaneswar.
5. The Executive Engineer © Postal Civil Division, Bhubaneswar.
- 6/8. The Executive Engineer © C.P.W.D Civil Division No I/II/III Bhubaneswar
- 9/11. The SDE© BSNL, Civil Sub Division No. I/II/III BBSR.
- 12/16. Notice Board/Auditor/AO/NIQ file/Spare copy. The Officer in charge of website www.odisha.bsnl.co.in for uploading please.

Encl: Quotation No: NIQ/**12/2019-20**/BCD/SDE-III/BBSR.

Sd/-
Executive Engineer (Civil)
BSNL Civil Division Bhubaneswar

SCHEDULE OF QUANTITIES

Name of the work : Dismantling of fallen roof top poles damaged by very severe cyclone "FANI" at various locations of Bhubaneswar City

Item No	Description of Item	Quantity	Unit	Rate (Rs)	Amount(Rs)
Sub-Head : LMR ITEMS					
1	Lifting of existing fallen 6.00Mt height roof top pole from hanging position by arranging pully, cutter, ropes or using any required tools with due care to avoid the damage of antena and other fixtures and stacking at site as per direction of E.I.C. (Rate for all operation to one Pole)	4.00	Each Job		
2	Lifting of existing fallen roof top pole structure from a very critical hanging position by arranging pully, cutter, ropes or using any required tools ,engaging expert skilled workers with due care to avoid the damage of antena and other fixtures and stacking at site as per direction of E.I.C. (Rate for all operation to one Pole)	1.00	Each Job		
3	Dismantling of existing fallen tower including removal of antena, cable and other fixtures and demolishing of cement concrete block of richer mix by mechanical means (using breaker) only carefully at any height of roof including disposal of rubbish by the head load beyond the premises as per direction of Engineer - in - charge. (Cost for one pole with its stays)	8.00	Each Job		

Contractor

Executive Engineer (C)
BSNL Civil Division
Bhubaneswar