



(A Govt. of India Enterprise)
OFFICE OF THE EXECUTIVE ENGINEER (CIVIL),
BSNL CIVIL DIVISION, DOOR SANCHAR BHAWAN, THIRD FLOOR, UNIT-IX,
BHUBANESWAR, PIN- 751022

SHORT NOTICE INVITING QUOTATION

Item rate quotations for the work as mentioned below are invited by the Executive Engineer (Civil), BSNL Civil Division, Bhubaneswar, 3rd floor, Unit-IX, Door Sanchar Bhawan, PIN: - 751022 for and on behalf of the BSNL for the following urgent work from registered Contractor.

1.0 The last date of receipt of application for issue of quotation forms (In prescribed format/ can also be downloaded from BSNL Website (www.odisha.bsnl.co.in) and date of issue of quotation forms will be as follows:

- I) Last date of receipt of application : **27.03. 2020 up to 15.00 Hrs.**
- II) Last date of issue of quotation forms : **27.03. 2020 up to 15.30 Hrs**

The last date of receipt of quotation is on **28.03. 2020** up to **15.00** hours. The quotation will be opened on the same day at **15.30** hours.

Envelope no.1 shall contain the license/registration copy, the copy of **PAN card** and GST registration signed by the applicant therein. Envelope no.2 shall contain the quotation bid/Financial bid. Envelope no.1 and Envelope no.2 shall be put in one covering envelope in top of which the name of work must be mentioned.

Sl. no	Name of Work	Estimated cost (Rs)	Time allowed
1.	Miscellaneous Civil maintenance works inside P&T Colony at Vanivihar, Bhubaneswar. Quotation No. NIQ/16/2019-20/BCD/SDE-II/BBSR.	80,835.00	15(Fifteen) days

TERMS AND CONDITIONS

1. The quoted rates shall be inclusive of all taxes i/c GST .
2. Payment will be made after completion the work as per the latest C.P.W.D specifications/as per direction of Engineer-in- Charge.
3. The authority reserves the right to accept/cancel any offer without assigning any reason thereof.
4. The offer shall remain valid for 5(**Five**) days.
5. The site of work is available.
6. The work being very urgent nature, the quotationer should start the work immediately after issue of work order in consultation with SDE(C), **BCSD-II**, BBSR. Hence, the quotationer should be prepared for the same
7. For approved make and approved shade/design, EE(C), BSNL Civil Division, BBSR may be contacted.
8. For any disputes arising out of it, if any, the decision of the Superintending Engineer(C), O/o CE(C), BSNL Civil Odisha Zone, Bhubaneswar shall be final and binding.

Sd/-

Executive Engineer(C)
BSNL civil Division
Bhubaneswar

Dated: **20.03.2020**

No. NIQ/16/2019-20/BCD/SDE-II/BBSR/117

Copy to:-

1. The C.G.M.T., BSNL Orissa Circle, Bhubaneswar-751001.
2. The GMTD, BSNL Telecom District, Bhubaneswar.
3. The Chief Engineer(C), BSNL Civil Odisha Zone, Bhubaneswar.
4. The Executive Engineer © Postal Civil Division, Bhubaneswar.
- 5/7 The Executive Engineer © C.P.W.D Civil Division No I/II/III Bhubaneswar
- 8/10. The SDE© BSNL, Civil Sub Division No. I/II/III BBSR.
- 11/16. Notice Board/Auditor/AO/NIQ file/Spare copy. The Officer in charge of website www.odisha.bsnl.co.in for uploading please.

Encl: Quotation No: **NIQ/16/2019-20/BCD/SDE-II/BBSR.**

Sd/-

Executive Engineer (Civil)
BSNL Civil Division Bhubaneswar

SCHEDULE OF QUANTITIES

Name of the work : Miscellaneous Civil maintenance works inside P&T Colony at Vanivihar, Bhubaneswar.

Sl. No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	Sub-Head : LMR ITEMS				
1	Labour charges for making partition using departmental aluminium partition section, particle board, glass panes, tapper clips, for erection partition frame work in position with necessary angle cleat, SS screws, pvc sleeves, dash hold fastener etc complete as per direction of Engineer in charge.	6.00	sqm	600.00	
2	Dismantling of old grill gate and grill and refixing the same in position with necessary welding by electric plant and anchoring the gate by angle holfast from side and top for firm holding all complete as per direction of EIC.	1.00	job	5000.00	
3	Chipping of surface of floors for removing loose concrete, mortar and other deposited particles including cleaning the surface all complete as per direction of E.I.C.	40.00	One Square Metre	42.00	
4	Providing and fixing mirror of superior glass (of approved quality) of required shape of thickness 6mm along with 9 mm thick hard board (marine ply) backing including necessary stainless stud/ CP brass screws etc complete.	3.00	One Square Metre	1974.00	
	Sub-Head : Dismantling and Demolishing				
5	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
a)	In cement mortar	0.20	One Cubic Metre	842.75	
6	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5.00	One Square Metre	20.05	
	Sub-Head : Concrete Work				
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
a)	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.40	One Cubic Metre	5466.30	
	Sub-Head : Brick Work				
8	Brick work with clay fly ash F.P.S. (non modular) brick of class designation 7.5 in superstructure above plinth level up to floor five level in :				

a)	Cement mortar 1:6 (1 cement :6 coarse sand)	1.10	One Cubic Metre	5269.05	
	Sub-Head : FLOORING Work				
9	Cost for using 20 mm thick cement mortar 1:4 (1 cement : 4coarse sand) bedding in laying of floor tiles and jointing with grey cement slurry @ 3.3kg/sqm(Tile will be supplied)	9.00	One Square Metre	466.45	
10	Fixing Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness. (Tile will be supplied)	43.00	One Square Metre	386.20	
	Sub-Head :Aluminium Work				
11	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):				
a.	With float glass panes of 5.50/6.00mm thickness	4.50	One Square Metre	1003.95	
12	Providing and fixing 100mm brass locks (best make of approved quality)of 6 leaver for aluminium doors including necessary cutting and making good etc. complete.	1.00	Each	359.00	
13	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :				
a)	150x10 mm	2.00	Each	65.35	
14	15 mm cement plaster on the rough side of single or half brick wall of mix :				
a)	1:6 (1 cement: 6 fine sand)	5.00	One Square Metre	172.80	
15	12 mm cement plaster of mix :				
a)	1:6 (1 cement: 6 fine sand)	1.00	One Square Metre	160.35	
16	Distempering with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.				
a)	Two or more coats on new work.	155.00	One Square Metre	53.15	
17	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :				

	Water thinnable cement primer.	105.00	One Square Metre	36.95	
	Sub-Head : Repairs to Buildings				
18	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	155.00	One Square Metre	8.35	
19	Renewing glass panes, with wooden fillets wherever necessary:				
a)	Float glass panes of thickness 4 mm .	0.50	One Square Metre	852.60	
20	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
a)	One or more coats on old work.	28.00	One Square Metre	48.50	
21	Distemping with 1st quality acrylic washable distemper (ready made) of approved manufacturer and of required shade and colour complete. as per manufacturer's specification.				
a)	One or more coats on old work.	60.00	One Square Metre	28.80	
22	Finishing walls with Acrylic Smooth exterior paint with of required shade :				
a)	Old work (Two or more coats applied @ 1.67 ltr/ 10 sqm) over existing cement paint surface.	100.00	One Square Metre	68.95	

Sd/-

Contractor

Executive Engineer (C)
BSNL Civil Division
Bhubaneswar