

**O/O the Executive Engineer (C)
BSNL Civil Division,
15 Cantonment Road, Cuttack,
Orissa, PIN 753001. PH: 0671-2303762 (O)**

NOTICE INVITING QUOTATION

NIQ No.01/2020-21/BSNL-CD/Cuttack/SD-BLS

Sealed cover quotation is invited by the Executive Engineer(C), BSNL Civil Division, Cuttack for and on behalf of BSNL from approved and eligible contractor of DOT/BSNL/CPWD/State PWD (B&R) & other registered contractors of allied department of state PWD/DOP/MES and Railway enlisted contractors for **“P/L Antistatic PVC sheet flooring in equipment room for Navy (NCN) at Chandipur, Balasore”** as per separate sheet attached herewith.

Interested contractors are requested to submit their quotation on or before **19.06.2020 upto 15.00 hrs** in the office of the Executive Engineer(C), BSNL Civil Division, 15 Cantonment Road, SSPO Building(1st Floor), Cuttack. The quotation will be opened by the Executive Engineer(C), BSNL Civil Division, Cuttack or by his authorized representative in presence of quotationers at 15.30 hrs on the same day.

The Executive Engineer(C), BSNL Civil Division, Cuttack reserves the right to reject any or all the quotations without assigning any reason thereof.

Executive Engineer(C),

BSNL Civil Division, Cuttack.
(For and on behalf of BSNL)

No. EE (C)-CK/Acs/Misc. Quotation/91 Dated 15.06.2020

Copy to:-

1. The Chief Engineer(C), BSNL, Civil Odisha Zone, Bhubaneswar.
2. The Accounts Officer (Claim), O/o the G.M.T.D, Cuttack.
3. The Sub-Divisional Engineer(C), BSNL, Civil Sub-Division-I, Cuttack.
4. The Sub-Divisional Engineer(C), BSNL, Civil Sub-Division-II, Cuttack.
5. The Jr. Accounts Officer, BSNL, Civil Division, Cuttack.
6. Notice Board.

Executive Engineer(C)

PRICE SCHEDULE

Name of work: P/L Antistatic PVC sheet flooring in equipment room for Navy (NCN) at Chandipur, Balasore

Si. No	Description of item	Quantity	Unit	Rate	Amount in Rs.
1	Providing and fixing 2.0 mm thick antistatic homogeneous PVC sheet plain coloured of approved quality (Wonder floor, Tusker, Krishna or equivalent) in flooring on sub-floor using rubber based adhesives of approved quality and manufacture like Dunlop S-758, Fevicol SR-998 or equivalent including cleaning the sub-floor, stretching the sheet, cutting, fitting, levelling and drying of base and rolling with light wooden roller weighing not less than 5.0 kg, connecting the carbon layer of the sheets with copper strips of minimum size 75x25mm at ends of all joints and connecting the strips with copper wire of approved diameter for making earthing all complete as directed by the Engineer-in-charge. (The finished surface area of vinyl flooring will be measured for payment)	13.00	Sqm		
2	Seam welding the antistatic/ plain PVC sheets in flooring longitudinally as well as transversely using PVC welding chord by hot welding air gun, cutting excess of welding chord, if any, making the surface smooth including cost of all materials, T&P, carriage complete as per direction of Engineer-in-charge.	11.00	Mt.		

Executive Engineer(C)
BSNL Civil Division,
Cuttack.