



(A Govt. of India Enterprise)

OFFICE OF THE EXECUTIVE ENGINEER (CIVIL),
BSNL CIVIL DIVISION, SAMBALPUR.
D.T.O. BUILDING, 4th FLOOR, KACHERI ROAD, SAMBALPUR
PIN-768001

NOTICE INVITING QUOTATION

The Executive Engineer(Civil), Bharat Sanchar Nigam Limited Civil Division, Sambalpur, D.T.O. Building, 4th Floor, Sambalpur, Odisha invites for and on behalf of [KENDU LEAVES , ODISHA](#) sealed item rate Quotation for the following work from eligible specialized firm having experience in Soil Testing. The firm should have expertise in conducting Soil Investigation.

1.0 The last date of receipt of applications for issue of quotation forms (In prescribed format/ can also be downloaded from BSNL Website www.orissa.bsnl.co.in) and date of issue of quotation forms will be as follows:

- I) Last date of receipt of application : **09.08.2018 up to 16.00 Hrs.**
- II) Last date of issue of quotation forms : **10.08.2018 up to 17.00 Hrs**

Quotation document consisting of plans & specifications, if any, the schedule of quantities of the various works to be done by the Contractor and other necessary documents, can either be down loaded from the BSNL website www.orissa.bsnl.co.in or may be seen in the office of the Executive Engineer (Civil), Bharat Sanchar Nigam Limited Civil Division, D.T.O. Building, 4th Floor, Sambalpur between 11.00 hours. & 16.00 hours from date **05.08.2018 to 09.08.2018** every day except on Sundays and Public Holidays.

Quotations, which should always be placed in sealed envelope, will be **received by** the Office of the E.E.(Civil) , BSNL Civil Division, Sambalpur **up to 15.00 Hrs. on date 13.08.2018** and will be **opened** by him or his authorized representative in his office on the same day at **15.30 Hrs.** Envelope no.1 shall contain details of credentials, GST registration details and copy of PAN Card signed by the agency therein. Envelope no.2 shall contain the quotation/Financial bid. Envelope no. 1 & 2 shall be put in the covering envelope in the top of which the name of work should be mentioned.

Sl. No	Name of Work	Estimated cost put to tender (Rs)	Earnest Money(Rs)	Time Allowed for completion
01	C/o D.F.O. (Kendu Leaves) Office Building at Khariar (SH-Soil Investigation)(NIQ No:210-22-18-01 Dated 03.08.2018)	25,404.00	Nil	07 (Seven) days

TERMS AND CONDITIONS

1. The quoted rates shall be inclusive of all taxes and levies payable under respective statute including GST. Quotationers who are liable to pay GST shall have valid registration.
2. Payment will be made after completion of work as per the latest CPWD specifications/as per direction of Engineer-in-charge.
3. The authority reserves the right to accept/reject any offer without assigning any reason thereof.
4. The offer shall remain valid for 07(Seven) days.
5. The Site of Work is available.
6. The work being very urgent in nature, the quotationer shall start the work immediately after issue of work order in consultation with the SDE (Civil), BSNL Civil Sub-division , Balangir.
7. The Items of work are incorporated in the "Schedule of Items". Work shall be executed as per the schedule of Items.
8. For any dispute arising out of it, if any, the decision of the Joint Chief Engineer (Civil), BSNL Civil Circle, Sambalpur shall be final and binding.

Sd/-

**Executive Engineer (Civil)
BSNL Civil Division
Sambalpur**

For and on behalf of [Kendu Leaves , Odisha](#)

No. 26(86)/CD-SBP/ 335

Dated: 03 /08/2018

Copy to:-For display on notice board for wide publicity:-

1. The C.G.M.T., BSNL Orissa Circle, Bhubaneswar-751001.
 2. The T.D.M., BSNL, Balangir.
 3. The Chief Engineer(C), BSNL Civil Odisha Zone, Bhubaneswar.
 4. The Joint Chief Engineer(C), BSNL Civil Circle, Sambalpur.
 5. The D.F.O.(K.L.), Khariar.
 - 6/7/8. The Executive Engineer©, BSNL Civil Division BBSR-I, II/Berhampur/ Cuttack
 9. The Executive Engineer © Postal Civil Division, Bhubaneswar.
 - 10/12. The Executive Engineer © C.P.W.D civil Division Bhubaneswar No I/II/III
 13. The Vigilance Officer, O/o the CGMT, Orissa Circle Bhubaneswar.
 - 14/19.The SDE© BSNL, Civil Sub division, Balangir.
 - 20/25 Notice Board/Cashier/Auditor/AO/NIQ file/Spare copy
- Encl: **NIQ No: 210-22-18-01 Dated 30.07.2018**

sd/-

**Executive Engineer (Civil)
BSNL Civil Division
Sambalpur**

<u>SCHEDULE OF QUANTITIES</u>						
Name of work :C/o D.F.O.(Kendu Leaves) Office Building at Khariar(SH-Soil Investigation)						
SI No	Description of Item	Quantity	Rate (Rs)	Unit	Amount (Rs)	
Sub-Head : Earth Work						
1	Boring 150 mm dia. bore hole through sand/clay/ silt strata at the location decided by the Engineer-in- charge by auger or shell and auger equipment as required.					
a)	From G.L. to 20.00 mtr	12.00		Meter		
2	Boring 150 mm dia bore hole with rotary drilling equipment with NX size diamond core drilling bit and double tube core barrel through soft/hard rock at the location decided by the Engineer in Charge.					
a)	From G.L. to 20.00 mtr (In ordinary rock)	2.00		Meter		
3	Collecting rock core samples approximately 54 mm dia at every 1.00 M or change of strata and determining RQD (Rock quality designation) and percentage core recovery.	2.00		each		

4	Carrying out standard penetration test in bore holes at various depth as per IS: 2131-1981	3.00		each		
5	Submitting detailed report alongwith definite recommendation on corresponding safe bearing capacity for depth of foundation viz. 2M, 3M, 4M,5M for width of foundation fiz 2M, 3M, 4M, 5M as well as type of foundation system (report shall be submitted in quadruplicate).	1.00		each job		

Executive Engineer(Civil)