

BHARAT SANCHAR NIGAM LIMITED
(A Government of India Enterprise)

TENDER DOCUMENT

Name of work:

Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar.

Total E.C.- Rs 58,64,205/-
(Civil part - Rs 57,05,524)
(Electrical part- Rs 1,58,681)

E.M.D.- Rs 1,17,290/-

Completion period: 5 (Five) months

NIT No-02/2018-19/BCD-II/EP/BBSR.

**O/o CHIEF ENGINEER (CIVIL)
BSNL ODISHA CIVIL ZONE
BHUBANESWAR**

I N D E X

Sl.No.	Details	Page		
		From	To	
01.	Cover page	01	-	01
02.	Index	02	-	02

PART-A.

03.	Information and Instructions to bidders for e-tendering	03	-	05
04.	Declarations to be given by the tenderers	06	-	06
05.	BSNL W-6:	07	-	16
06.	BSNL W-7/8 (Abridged form):	17	-	19

PART-B (FOR CIVIL WORK COMPONENT)

07.	a) Proforma of Schedule A to F for civil work	20	-	24
	b) Schedule "D" for civil work	25	-	45
	c) Schedule "A" for civil work	46	-	51

PART-C (FOR ELECTRICAL WORK COMPONENT)

08.	a) Proforma of Schedule A to F of Electrical work	52	-	55
	b) Eligibility Criteria for Electrical work	56	-	56
	c) Schedule "D" for Electrical work	57	-	62
	c) Schedule "A" for Electrical work	63	-	68

The D.N.I.T. contains 68 (Sixty Eight) pages only.

PART – A
INFORMATION AND INSTRUCTIONS TO BIDDERS FOR e-TENDERING

The Executive Engineer(Civil), [BSNL Civil Division-II](#), Bhubaneswar invites item rate e-tenders on behalf of [NANDANKANAN BIOLOGICAL PARK](#) from approved and eligible contractors of BSNL (Civil Wing) and non-BSNL registered contractors of appropriate class of Public Works Organizations like CPWD, DOP, MES, Railways and State PWD (B&R) of Odisha for the following work:

Sl.No. Description Details

NIT No. 02/2018-19/BCD-II/EP/BBSR.

Name of Work: **Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar.**

- i. Estimated Cost **Rs 58,64,205/-**
[Rs 57,05,524 (Civil part)+Rs 1,58,681(Electrical part)]
 - ii. Earnest Money (In Rs.) : **Rs 1,17,290/-**
 - iii. Period of Completion : **5 (Five) months**
 - iv. Last date and time of online submission of tender: 18.00 hours on -02.11.2018
 - v. Time and date of online opening of Documents: 15.30 hours on- 05.11.2018
 - vi. Time and date of opening of Online Financial Bids : 15.30 hours on 09.11.2018
 - vii. Period during which hard copies of EMD, Registration Certificates, Undertaking and other Documents to be submitted to Division-II office these by only the lowest Tenderer. To be submitted during office hours within a week from the date of opening of Financial Bid. In case the last day happens to be closed holiday, Documents shall be submitted on the next working day.
1. The intending bidder must read the terms and conditions of Tender document carefully. He should submit his bid if he considers himself eligible and he is in possession of all the certificates / documents required.
 2. Information and Instructions for bidders for e-tendering posted on website shall form part of bid document.
 3. The bid document consisting of NIT, plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents can be seen and downloaded from <http://www.tenderwizard.com/BSNL> or www.orissa.bsnl.co.in free of cost. Any corrigendum(s) will be uploaded in these two web sites and no press publicity will be given for the corrigendum(s).

DNIT

The tenderers are requested to verify the corrigendum(s), if any before submitting the online bid.

4. But the bid can be submitted only after depositing e-tender Processing Fee in favour of ITI Limited and uploading the mandatory scanned documents as specified. The scanned copy of Demand Draft or Pay order or Banker's Cheque or Deposit at call Receipt or Fixed Deposit Receipts or Bank Guarantee of any Scheduled Bank towards EMD in favour of **Accounts Officer (A&P), O/o CGM, BSNL, Bhubaneswar** is also to be uploaded.
5. Those contractors not registered on the website mentioned above, are required to get registered beforehand. If needed they can be imparted training on online bidding process as per details available on the website.
6. The intending bidder must have valid class-III digital signature to submit the bid. After submission of the bid online the contractor can re-submit revised bid any number of times but before last time and date of submission of bid as notified. While submitting the revised bid, contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last time and date of submission of bid as notified.
7. On opening date, the contractor can login and see the bid opening process. After opening of bids he will receive the competitor bid sheets.
8. Contractor can upload documents in the form of JPG format, PDF format and any other format as permissible by the e-tendering portal.
9. Contractor must ensure to quote rate of each item. The column meant for quoting rate in figures appears in dark yellow colour and the moment rate is entered, it turns sky blue.
In addition to this, while selecting any of the cells a warning appears that if any cell is left blank the same shall be treated as "0".
Therefore, if any cell is left blank and no rate is quoted by the bidder, rate of such item shall be treated as "0" (ZERO).
10. If the contractor is found ineligible after opening of bids, his bid shall become invalid and e-Tender Processing Fee shall not be refunded.
11. For the Eligibility Documents uploaded online, if any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically by the contractor the bid shall become invalid and e-Tender Processing Fee shall not be refunded.
12. Copy of Enlistment Order and certificate of work experience and other eligibility documents as specified in the Notice Inviting Tender shall be scanned and uploaded to the e-tendering website within the period of tender submission. However, certified copy of all the scanned and uploaded documents as specified shall have to be submitted by the lowest bidder along with physical EMD (of the scanned copy of EMD) uploaded within ONE WEEK physically in the office of tender opening authority.

List of eligibility Documents to be scanned and uploaded within the period of bid submission:

- a) Certificate of registration / enlistment order
- b) Treasury Challan/Demand Draft/Pay order or Banker`s Cheque /Deposit at Call Receipt/FDR/ Bank Guarantee of any Scheduled Bank against EMD.
- c) Certificate of GST registration
- d) Certificates of Work Experience (for non BSNL registered contractors).
- e) If the bidder is a firm in partnership/ company, then the hard copies of **Form "A" and partnership deed in case of partnership firms /memorandum of articles of association and power of attorney or authorization to the person who signs the tender in case of companies.**
- f) **An undertaking that "The Physical EMD shall be deposited by me/us with the EE calling the bid in case I/we become the lowest bidder within ONE WEEK of the opening of financial bid otherwise BSNL may reject the bid and also take action to withdraw my/our enlistment/debar me/us from tendering in BSNL."**

Note:- The tenderers are requested not to upload any other certificates or documents. Only the required experience certificates are to be uploaded.

DECLARATIONS TO BE GIVEN BY THE TENDERERS

It is to certify that

- a) I /We have gone through BSNL W-8 amended up to correction Slip No.6 as available on website www.orissa.bsnl.co.in or in the office of Executive Engineer(c) and I/We agree with the terms and conditions of it and understood that it will form part of the agreement.

Date: -

Signature of the Tenderer

- b) "I,S/o Shri resident of hereby certify that none of my relative(s) as defined in para 15 of BSNL W-6 is/are employed in BSNL Civil Zone, Odisha. In case at any stage, it is found that the information given by me is false/incorrect, BSNL shall have the absolute right to take any action as deemed fit without any prior intimation to me".

NOTE: - (To be certified by all the partners in case of partnership firms, by all the directors in case of companies).

Date: -

Signature of the Tenderer

1. Other partners 2. Sri _____ S/o Sri _____ Signature:
3. Sri _____ S/o Sri _____ Signature:
4. Sri _____ S/o Sri _____ Signature:

- c) **"The Physical EMD shall be deposited by me/us with the EE calling the bid in case I/we become the lowest bidder within ONE WEEK of the opening of financial bid, otherwise BSNL may reject the bid and also take action to withdraw my/our enlistment/debar me/us from tendering in BSNL."**

Signature of the Tenderer

**BHARAT SANCHAR NIGAM LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)****NOTICE INVITING e-TENDER**

The Executive Engineer (Civil), BSNL **Civil Division-II**, Bhubaneswar invites Item rate e-tenders on behalf of **NANDANKANAN BIOLOGICAL PARK** from approved and eligible contractors of BSNL (Civil Wing) and non-BSNL registered contractors of appropriate class of Public Works Organizations like CPWD, DOP, MES, Railways and State PWD (B&R) of Odisha for the work of : **Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar.**

1. The enlistment of the contractors should be valid on the last date of submission of bids. In case the last date of submission of bid is extended, the enlistment of contractor should be valid on the original date of submission of bids.

The intending bidder eligible to submit bid has to scan and upload the following documents within the period of bid submission:

List of eligibility Documents to be scanned and uploaded within the period of bid submission:

- a) Certificate of registration / enlistment order
- b) Treasury Challan/Demand Draft/Pay order or Banker`s Cheque /Deposit at Call Receipt/FDR/ Bank Guarantee of any Scheduled Bank against EMD.
- c) Certificate of GST registration.
- d) Certificates of Work Experience (for non BSNL registered contractors).
- e) If the bidder is a firm in partnership/ company, then the hard copies of **Form "A" and partnership deed in case of partnership firms /memorandum of articles of association and power of attorney or authorization to the person who signs the tender in case of companies.**
- f) **An undertaking that "The Physical EMD shall be deposited by me/us with the EE calling the bid in case I/we become the lowest bidder within ONE WEEK of the opening of financial bid otherwise BSNL may reject the bid and also take action to withdraw my/our enlistment/debar me/us from tendering in BSNL."**

Note:- The tenderers are requested not to upload any other certificates or documents. Also only the required experience certificates are to be uploaded.

- 1.1 The work is estimated to cost **Rs 58,64,205/- (Part A: Major component-Civil Portion: Rs. 57,05,524/- + Part B: Minor component - Electrical Portion: Rs.1,58,681/-)**. This estimate, however, is given merely as a rough guide.

1.2 Intending bidder is eligible to submit the bid provided he has definite proof from the appropriate authority, which shall be to the satisfaction of the competent authority, of having satisfactorily completed similar works of magnitude specified below:

1.2.1 Criteria of eligibility for submission of bid document for non-BSNL registered contractors of appropriate class of Public Works Organizations like CPWD, DOP, MES, Railways and State PWD (B&R) of Odisha.

1.2.1.1 for works up to Rs.7 lakhs : ----NIL----

1.2.1.2 for works above Rs 7 lakhs and up to Rs. 5 Cr:

The applicant should have completed works as per details below during the last seven years ending last day of the month previous to the one in which the tenders are invited.

a) Three similar completed works each costing not less than the amount equal to **40% of estimated cost.**

or

b) Two similar completed works each costing not less than the amount equal to **50% of estimated cost.**

or

a) One similar completed works costing not less than the amount equal to **80% of estimated cost.**

Similar work means 'Building works or RCC works" The value of executed works shall be brought to current costing level by enhancing the actual value of executed work at simple rate of 7% per annum; calculated from the date of completion to last date of submission of tenders and shall be rounded off to the nearest hundred rupees. **Above works should have been carried out in Central Government/ Central Public Sector Undertakings.** The experience certificate given by an officer not below the rank of Executive Engineer, shall indicate clearly the nature of the work and the satisfactory completion of the work along with value of work done and actual date of completion and shall be in original / attested. Certificates indicating annual turnover or different works done under a rate contract /annual contract shall not be considered as one work. *Certificates without satisfactory completion and/ or actual date of completion will be considered as invalid.*

2. Agreement shall be drawn with the successful tenderer on prescribed Form No.BSNL W-7/8 amended up to correction slip no.6, which is available on BSNL website : www.orissa.bsnl.co.in or in the office of the **Executive Engineer (Civil),BSNL Civil Division-II,Bhubaneswar.** Tenderer shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.

3. The time allowed for carrying out the work will be **5 (Five) months** and shall be reckoned from **10th day** after the date of issue of **letter of acceptance** of the tender or from the first day of the handing over of the site whichever is later, in accordance with phasing, if any, indicated in the tender document.

4. The site for the work is available.
- (i) The architectural and structural drawings shall be made available in phased manner, as per requirement of the same as per approved programme of completion submitted by the contractor after award of work.**
5. The bid document consisting of NIT, plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents can be seen and downloaded from [http:// www.tenderwizard.com/BSNL](http://www.tenderwizard.com/BSNL) and the NIT & General conditions of contract upto Correction Slip No.6 can be seen from BSNL website www.orissa.bsnl.co.in or in the office of the Executive Engineer (Civil ,BSNL Civil Division-II,Bhubaneswar.
6. After submission of the bid the contractor can re-submit revised bid any number of times but before last date and time of submission of bid as notified.
7. While submitting the revised bid, contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last date and time of submission of bid as notified.
8. **Earnest Money in the form of Treasury Challan or Demand Draft or Pay order or Banker's Cheque or Deposit at Call Receipt or Fixed Deposit Receipt drawn in favour of Accounts Officer (A&P), O/o CGM, BSNL, Bhubaneswar shall be scanned and uploaded to the e-Tendering website within the period of bid submission.**

A part of earnest money is acceptable in the form of bank guarantee also. When amount of earnest money is more than Rs. 5 lakhs, part of the earnest money is acceptable in the form of Bank Guarantee also. In such case, minimum 50% of earnest money (but not less than Rs. 5 lakh) or Rs. 25 lakh, whichever is less, will have to be deposited in the shape prescribed above. And balance **may be deposited** in shape of Bank Guarantee of any scheduled bank **having validity for six months or more from the last date of receipt of bids. The EMD has to be scanned and uploaded to the e-Tendering website by the intending bidders within the period of bid submission.**

The physical EMD (of the scanned copy of EMD) uploaded shall be deposited by the lowest bidder within ONE WEEK after opening of financial bid failing which the bid shall be rejected and enlistment of the agency shall be withdrawn by the enlisting authority. The agency shall be debarred from tendering in BSNL.

The following undertaking in this regard shall also be uploaded by the intending bidders:-

"The Physical EMD shall be deposited by me/us with the EE calling the bid in case I/we become the lowest bidder within a week of the opening of financial bid otherwise Organization may reject the bid and also take action to withdraw my/our enlistment/debar me/us from tendering in BSNL."

Interested contractor who wish to participate in the bid has also to make following payments within the period of bid submission:

e-tender Processing Fee: e-Tender Processing Fee amounting to Rs. 3460/- is to be paid through online to the account of M/s ITI Limited through their e-gateway by credit/debit card, internet banking or RGTS/NEFT facility. E-Tender processing fee paid through Demand draft shall not be accepted.

The intending bidder has to fill all the details of Demand Draft or Pay order or Banker's Cheque or Deposit at call Receipt or Fixed Deposit Receipts and Bank Guarantee (bankers name, amount, number and date) against payments for EMD in the drop down menu of the e-tendering portal.

Copy of Enlistment Order and certificate of work experience and other documents as specified in the notice shall be scanned and uploaded to the e-Tendering website within the period of bid submission. ***However, SELF certified copy of all the scanned and uploaded documents as specified in notice shall have to be submitted by the lowest bidder along with physical EMD within ONE WEEK physically in the office of tender opening authority.***

Online bid documents submitted by intending bidders shall be opened only of those bidders, ***who has deposited e-Tender Processing Fee with M/s ITI Limited and Earnest Money Deposit and other documents scanned and uploaded are found in order.***

The bid submitted shall be opened at 15.30 Hrs on 05.11.2018 and financial bid shall be opened at 15.30 Hrs on 09.11.2018

9. The bid submitted shall become invalid and e-Tender processing fee shall not be refunded if:
 - (i) The bidder is found ineligible.
 - (ii) The bidder does not upload all the documents (including GST registration) as stipulated in the bid document ***including the undertaking about deposition of physical EMD of the scanned copy of EMD uploaded.***
 - (iii) If any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted ***physically by the lowest bidder*** in the office of bid opening authority.
 - (iv) In case the eligibility credentials are not found genuine at any stage i.e. before award of work or during execution of the work or after completion of the work, the contractor will be debarred from tendering in BSNL for three years including any other action under the contract or existing law
 - (v) ***The lowest bidder does not deposit physical EMD within a week of opening of bid.***
10. In case of works having estimated cost below Rs. 15,00,000/-, the successful tenderer shall be required to execute an agreement with the Engineer-in-charge in the performa annexed to the tender document, within 15 days of the issue of letter of award by the BSNL. In the event of failure on the part of the successful tenderer to sign the agreement, the earnest money will be forfeited and tender cancelled. In case of works of estimated to cost Rs.15,00,000/- and above, the successful tenderer, upon issue of letter of acceptance of Tender, shall be

required to furnish Performance Guarantee @ 5% of the tendered value in the form of irrevocable Bank Guarantee of requisite amount to the

Engineer-in-charge in the Performa annexed to the tender document, within 10 days of the issue of letter of award of Tender by BSNL. In the event of failure on the part of the successful tenderer to furnish the Bank Guarantee within 10 days, including the extended period if any, the earnest money deposited by the contractor shall be forfeited automatically without any notice to the contractor, and tender will be cancelled.

11. The description of the work is as follows:

Foundation-Pile foundation, RCC bottom of Shed-RCC slab frame, Roof of Shed-Steel truss Galvaluminium roof sheets.

Intending Bidders are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their bids as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. A bidder shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charge consequent on any misunderstanding or otherwise shall be allowed. The bidder shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by a bidder implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and of conditions and rates at which stores, tools and plant, etc. will be issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.

12. The competent authority on behalf of BSNL does not bind himself to accept the lowest or any other bid and reserves to itself the authority to reject any or all the bids received without the assignment of any reason. All bids in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the bidders shall be summarily rejected.
13. Canvassing whether directly or indirectly, in connection with bidders is strictly prohibited and the bids submitted by the contractors who resort to canvassing will be liable for rejection.
14. The competent authority on behalf of BSNL reserves to himself the right of accepting the whole or any part of the bid and the bidders shall be bound to perform the same at the rate quoted.
15. The company or firm or any other person shall not be permitted to tender for works in BSNL Civil Zone in which his near relative (s) (directly recruited or on deputation in BSNL) is/are posted in any capacity either non-executive or executive employee. Near relative (s) for this purpose is/are defined as:
 - (i) Member of Hindu Undivided family (HUF).
 - (ii) They are Husband and Wife.

(iii) The one is related to other in the manner as father, mother, son(s) & Son's wife (daughter-in-law), Daughter(s), Daughter's husband (son-in-law), brother(s), brother's wife, sister(s), sister's husband (brother-in-law).

The contractor shall also intimate the names of persons who are working with him in any capacity or are subsequently employed by him and who are near relative to any executive employee/ Gazetted officer in the BSNL or Department of Telecom or in the Ministry of Communications.

All the intending tenderers will have to give a certificate that none of his/her such near relative(s) as defined above is/are working in the concerned BSNL Civil Zone where he is going to apply for tender/work. The format of the certificate is as under:

"I, _____ s/o Shri _____ Resident of _____ hereby certify that none of my relative (s) as defined above is/are employed in concerned BSNL Civil Zone. In case at any stage, it is found that the information given by me is false/incorrect, BSNL shall have the absolute right to take any action as deemed fit without any prior intimation to me".

The certificate in case of Proprietorship Firm shall be given by the proprietor, for Partnership Firm certificate shall be given by all partners and in case of Limited Company, by all Directors of the company. However, Government of India / Financial Institutions nominees and independent non-official part-time Directors appointed by Govt. of India or the Governor of the State are excluded from the purview of submission of this certificate while submitting tenders by Limited Companies.

Any breach of these conditions by the Company or Firm or any other person, the tender/work will be cancelled and Earnest Money/ Security Deposit/Performance guarantee will be forfeited at any stage, whenever it is so noticed. BSNL will not pay any damages to the company or Firm or the concerned person but damages arising on account of such cancellation to be borne by the contractor. The Company or Firm or the person will also be debarred for further participation in the tender in the concerned BSNL Civil Zone. Further, any breach of this condition by the tenderer would also render him liable to be removed from the approved list of contractors or BSNL. If however the contractor is registered in any other Department he shall also be debarred from tendering in BSNL for any breach of this condition.

16. No Engineer of Gazetted rank or other Gazetted Officer employed in engineering or administrative duties in an Engineering Department of the Government of India/State Government or PSU's is allowed to work as a contractor for a period of two years after his retirement from Govt. service, without previous permission of the Govt. of India or BSNL in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Govt. of India/State Government or PSU's as aforesaid before submission of the tender or engagement in the contractor's service.
17. The tender for the work shall remain open for acceptance for a period of **45(Forty Five) days** from the date of opening of the tenders. If any tenderer withdraws his tender before the said period or issue of letter of acceptance, whichever is earlier, or, makes any modifications in the terms and conditions of the tender which are

not acceptable to the BSNL, then the BSNL shall, without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money as aforesaid.

18. This Notice Inviting Tender (BSNL W-6) shall form a part of the Contract Document. In accordance with clause 1 of the contract, the letter of acceptance shall be issued first in favour of the successful Tenderer/Contractor. After submission of the performance guarantee, the letter of award shall be issued. The contract shall be deemed to have come into effect on issue of letter of acceptance of the tender. On issue of letter of award, the successful Tenderer/Contractor shall, within 15 days from such date, formally sign the agreement consisting of: -
 - a) The Notice Inviting Tender, all the documents including additional conditions, specifications and drawings, if any, forming part of the bid as uploaded at the time of invitation of bid and the rates quoted online at the time of submission of bid and acceptance thereof together with any correspondence leading thereto.
 - b) Standard BSNL W-7/8 updated upto correction slip no-6 as on BSNL website www.orissa.bsnl.co.in
 - c) Agreement signed on non-judicial stamp paper as per Performa annexed to the tender document.
19. Payment to the contractors shall be *made by the BSNL* through e-payment system like ECS & EFT as detailed below:
 - (a) In cities/areas where ECS/EFT facility is provided by Banks, the tenderer must have Account in such ECS/EFT facility providing Banks and that Bank A/c No shall be quoted in the tender by the tenderer
 - (b) The cost of ECS/EFT will be borne by BSNL in all cases where the payment to contractor is made in a local Branch i.e. tenderer is having bank account in the same place from where the payment is made by BSNL unit.
 - (c) In case payment is made to outside branch i.e. tenderer is having bank account not in the same place from where the payment is made by BSNL unit, the crediting cost will have to be borne by the tenderer only.
 - (d) The payments to contractors will compulsorily be made through ECS/EFT in respect of all contracts where the value of the contract is more than Rs. 10 lakhs.
20. *The bills shall be submitted by the contractor in Computerized Measurement Books(CMB) as per procedure laid down in Clause 6A of BSNL W-8 which will form part of the agreement. The bills shall be submitted by the contractor by 25th of every month.*
21. First running account bill shall be paid only after
 - (a) signing of the Agreement/Contract by both the parties, and
 - (b) Progress chart has been prepared as required under Clause 5 and approved by the competent authority and
 - (c) After obtaining labour licence, EPF Registration, ESIC Registration, whatever applicable in this three for this contract or the contractor.
22. General conditions of contract for works amended upto Correction Slip No. 6 in BHARAT SANCHAR NIGAM LIMITED are available on BSNL website www.orissa.bsnl.co.in as well as in the office of the Executive Engineer.

23. For e-Tendering of this tender BSNL has engaged e-portal maintained by M/s ITI, New Delhi. The agency intending to participate in tendering process shall have to register with ITI, New Delhi.
24. The intending bidder can get registered with ITI, New Delhi. For details kindly visit website <http://www.tenderwizard.com/BSNL> or contact Shri SANJIB MOHAPATRA mobile no 9937488749 or 7377708585.
25. If any terms and conditions under General Rules and Directions, (which can be seen in general conditions of contract available in BSNL website www.orissa.bsnl.co.in) is in contravention to terms and conditions as above, the terms and conditions as above shall prevail.

26.0 FOR COMPOSITE TENDERS

- 26.1.1 The Executive Engineer in charge of the major component will call tenders for the composite work. The cost of the tender document and earnest Money will be fixed with respect to the combined estimated cost put to tender for the composite tender.
- 26.1.2 The tender document will include following three components:
 - Part A: BSNL W-6, BSNL W- 7/8, standard General Conditions of Contract for BSNL as applicable with all amendments/modifications upto date.
 - Part B: Pro forma for Schedule A to F for major component of work, Special conditions, Additional conditions (General / Civil works), particular specifications, list of recommended makes of Materials for civil works, schedule of quantities etc.
 - Part C: Pro forma for Schedule A to F for minor component of the work. (CE /SE / EE in charge of major component shall also be competent authority under clause 2 and clause 5 as mentioned in Schedule A to F for minor components), General / specific conditions, specifications for electrical works, list of recommended makes of materials for electrical works, schedule of quantities etc..
- 26.1.3 The tenderer must associate with himself, agencies of the appropriate class eligible to tender for electrical sub head, meeting the eligibility criteria as mentioned in Part C. *In case the main contractor himself meets the required eligibility criteria he shall be allowed to execute the electrical work after due verification etc. The main contractor shall give detailed execution programme of the work in which he shall indicate the time/stage of work when the agency for the electrical work will be deployed by him.*
- 26.1.4 The eligible tenderers shall quote rates for all items of major component as well as for all items of minor components of work. The lowest tenderer would be decided based on the total amount quoted in respect of both **CIVIL** and **ELECTRICAL** Schedules in the tender documents. It will be obligatory on the part of the tenderer to sign the tender document for all the components (The schedule of quantities, conditions and special conditions etc.)

- 26.1.5 After acceptance of the tender by competent authority, the EE in charge of major component of the work shall issue letter of award on behalf of BSNL. After the work is awarded, the main contractor will have to enter into one agreement with EE in charge of major component and has also to sign two or more copies of agreement depending upon number of EEs in charge of minor components. One such signed set of agreement shall be handed over to EE in charge of minor component. EE of major component will operate Part-A and Part-B of the agreement. EE-in-charge of minor component(s) shall operate Part-C along with Part A of the agreement.
- 26.1.6 Entire work under the scope of composite tender including major and minor components shall be executed under one agreement.
- 26.1.7 Security Deposit will be worked out separately for each component corresponding to the estimated cost of the respective component of works. The Earnest Money will become part of the security deposit of the major component of work.
- 26.1.8 The main contractor has to associate agency(s) for minor component(s) conforming to eligibility criteria as defined in the tender document and has to submit detail of such agency(s) to Engineer-in-charge of minor component(s) within prescribed time. Name of the agency(s) to be associated shall be approved by Engineer-in-charge of minor component(s). If the main contractor fails to associate agency for execution of electrical work within the said period or furnishes incomplete details or furnishes details of ineligible agencies the entire scope of electrical work shall be withdrawn from the tender and the same shall be got executed by the Engineer-in-charge at the risk and cost of the main contractor.
- 26.1.9 In case the main contractor intends to change any of the above agency/agencies during the operation of the contract, he shall obtain prior approval of Engineer-in-charge of minor component. The new agency/agencies shall also have to satisfy the laid down eligibility criteria. In case Engineer-in-charge of minor component(s) is not satisfied with the performance of any agency, he can direct the contractor to change the agency executing such items of work and this shall be binding on the contractor.
- 26.1.10 The main contractor has to enter in to agreement with contractor(s) associated by him for execution of minor component(s). Copy of such agreement shall be submitted to EE in charge of each minor component as well as to EE in charge of major component. In case of change of associate contractor, the main contractor has to enter into an agreement with the new contractor associated by him.
- 26.1.11 Running payment for the major component shall be made by EE of major discipline to the main contractor. Running payment for minor components shall be made by the Engineer-in-charge of the discipline of minor component directly to the main contractor.

In case main contractor fails to make the payment to the contractor associated by him within 15 days of receipt of each running account

payment then on the written complaint of the contractor associated for such minor component, EE in charge of minor component shall serve the show cause to the main contractor and after considering the reply of the same he may make the payment directly to the contractor associated for minor component as per the terms and conditions of the agreement drawn between main contractor and associate contractor fixed by him, if reply of main contractor either not received or found unsatisfactory. Such payment made to the associate contractor shall be recovered by EE of major or minor component from the next RA/final bill due to main contractor as the case may be.

26.1.11A The composite work shall be treated as complete when all the components of the work are complete. The completion certificate of the composite work shall be recorded by Engineer-in-charge of major component after record of completion certificate of all other components.

26.1.11B Final bill of whole work shall be finalized and paid by the EE of major component. Engineer(s) in charge of minor component(s) will prepare and pass the final bill for their component of the work and pass on the same to the EE of major component for including in the final bill for composite contract.

Signature and Name of

Executive Engineer (Civil)
For & on behalf of the
NANDANKANAN BIOLOGICAL PARK.

BHARAT SANCHAR NIGAM LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)

STATE: ODISHA

CIRCLE: BHUBANESWAR

DIVISION-II: BHUBANESWAR

ZONE: ODISHA

SUB-DIVISION-VI: BHUBANESWAR

Percentage Rate Tender / Item Rate Tender & Contract for Works:

(A) Tender for the work of: **Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar.**

(i) To be submitted by 18.00 hours on 02.11.2018 (date)

(ii) To be opened in presence of tenderer who may be present at 15.30 hours on 05.11.2018 in office of Executive Engineer (Civil) and financial bid shall be opened at 15.30 Hrs on 09.11.2018.

TENDER

I/ We have read and examined notice inviting tender, schedule, A, B, C, D, E & F. specifications applicable, Drawings & Design, General Rules and Directions, Conditions of Contract, Clauses of Contract, Special conditions, Schedule of Rate & other documents forming part of the bid as uploaded at the time of invitation of bid and the rates quoted online at the time of submission of bid and Rules referred to in the Conditions of Contract and all other contents in the tender document for the work.

I/ We hereby tender for the execution of the work specified for the **Nandan Kanan Biological Park** within the time specified in schedule 'F', viz., schedule of quantities and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule-1 of General Rules and Directions and in Clause 11 of the Conditions of the contract and with such materials as are provided for, by and in respect in accordance with, such conditions so far as applicable.

I/ We agree to keep the tender open for **45 (Forty Five) days** from the due date of submission thereof and not to make any modifications in its terms and conditions. If I/we withdraw my/our tender before the said period or issue of letter of acceptance, whichever is earlier, or, makes any modifications in the terms and conditions of the tender which are not acceptable to the BSNL, then the BSNL shall, without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money as aforesaid.

A sum of Rs **1,17,290/-** (Rupees One Lakh Seventeen Thousand Two hundred Ninety) only has been deposited in prescribed manner as earnest money.

If I/We fail to commence the work specified, I/We agree that the said Bharat Sanchar Nigam Limited shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely otherwise the said earnest money shall be retained by competent authority on behalf of the Bharat Sanchar Nigam Limited

DNIT

towards Security Deposit to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to therein and carry out such deviations as may be ordered, upto maximum of the percentage mentioned in Schedule 'F' and those in excess of that limit at the rates to be determined in accordance with the provision contained in Clause 12.2 and 12.3 of the tender form.

I/We agree that, in case of works of estimated cost exceeding Rs.15,00,000/-, to deposit an amount equal to 5% of Tendered value of the work as performance guarantee in the form of bond of any Scheduled Bank of India in accordance with the proforma prescribed or in the form of Fixed Deposit Receipt etc., within **07 days** of the issue of letter of acceptance of Tender by the BSNL. I/We am/are aware that in the event of failure on my/our part to furnish the Bank Guarantee within **07 days**, the earnest money will be forfeited and tender cancelled.

I/ We hereby intimate that for receiving payments I/we have an account in _____ Bank with account No. _____ where the ECS/EFT facility of e-payment is available.

I/We hereby declare that I/We shall treat the tender documents drawings and other records connected with the work as secret/confidential documents and shall not communicate information derived there-from to any person other than a person to whom I/We am/are authorised to communicate the same or use the information in any manner prejudicial to the safety of the State.

I/We agree that should I/We fail to commence the work specified in the above memorandum, an amount equal to the amount of the earnest money mentioned in the form of invitation of tender & performance guarantee shall be absolutely forfeited to the Bharat Sanchar Nigam Limited and the same may at the option of the competent authority on behalf of the Bharat Sanchar Nigam Limited be recovered without prejudice to any right or remedy available in law out of the deposit/ performance guarantee in so far as the same may extend in terms of the said bond/guarantee and in the event of deficiency out of any other money due to me/us under this contract or otherwise.

The information in respect of works in hand is as per proforma enclosed.

"I/we agree that this contract is subject to jurisdiction of Court at **Bhubaneswar** only."
(Where the NIT/Tender has been issued)

Dated.....

Witness:

Address:

Occupation:

()

Signature of Contractor

Postal Address: -

DNIT

ACCEPTANCE

The above tender (as modified by you (Contractor) and as provided in the letters mentioned hereunder) is accepted by me for and on behalf of the Odisha Forestry Sector Development Society for a sum of Rs _____ (Rupees _____)

The letters referred to below shall form part of this Contract Agreement:-

- (a) _____
- (b) _____

For & on behalf of the **NANDANKANAN BIOLOGICAL PARK.**

Signature _____

Dated.....

Name and designation

DNIT

PART – B (FOR CIVIL WORK COMPONENT)

PROFORMA OF SCHEDULES

(Operative Schedules to be supplied separately to each of the intending tenderer)

SCHEDULE “A”

Schedule of Quantities - ENCLOSED

SCHEDULE “B”

Schedule of Materials to be issued to the contractor

S. No.	Description of Item	Quantity	Rates in figures & words at which the materials will be charged from the contractor	Place of issue
1	2	3	4	5
NIL				

SCHEDULE “C”

Tools and Plants to be hired to the contractor

S. No.	Description of Item	Hire charges per day	Place of issue
1	2	3	4
DELETED			

SCHEDULE “D”

Extra schedule for specific requirements/documents for the work, if any.

1. List of Preferred makes for various items of work
2. Additional Conditions of contract.
3. Additional Conditions(General)
4. Conditions for other Taxes and Royalties.

SCHEDULE “E”

Schedule of component of Materials, Labour etc. for escalation.

CLAUSE 10

Component of Materials expressed as percent of Total Value of Work	“X”	75%
Component of Labour expressed as percent of Total Value of Work	“Y”	25%
Component of POL expressed as percent of Total Value of Work	“Z”	0%

DNIT

SCHEDULE "F"

(Reference to General Conditions of Contract)

Name of Work: - "Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar."

Estimated cost of Work: **Rs 57,05,524/- (Civil Part)**

Earnest Money **Rs 1,17,290 (Rupees One Lakh Seventeen Thousand Two hundred and Ninety only)**

Performance Guarantee

(5 % of the tendered value in the form of Bank Guarantee from Scheduled Bank in respect of works with estimated cost put to tender exceeding Rs.15 Lakhs)

Rs_____***_____(
Rupees_____***_____)

(It shall be deposited within 07 days from the date of issue of letter of acceptance by the EE@, which can also be extended to a specified period as per the discretion of the NIT approving authority).

Security Deposit

(5 % of the tendered value of civil part in the form of Bank Guarantee from Scheduled Bank in respect of works)

Rs_____
(Rupees_____)

Officer inviting tender

Executive Engineer (Civil),
BSNL Civil Division-II, Bhubaneswar.

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with Clause 12.2 & 12.3

50%

Definitions

2(v) Engineer-in charge

See below

Executive Engineer (Civil),
BSNL Civil Division-II, Bhubaneswar.

2(viii) Accepting Authority

**SUPERINTENDING ENGINEER(C) /
CHIEF ENGINEER(C),
BSNL CIVIL ODISHA ZONE,
BHUBANESWAR.**

2(x) Percentage on cost of materials and labour to cover all overheads and profit

15 %

2(xi) Standard Schedule of Rates

Central Public Works Department
Delhi Schedule of rates - 2016 with
up to date correction slips.

DNIT

9(ii) Standard BSNL Contract Form

BSNL W 7/8 form as amended upto and including correction slip No.6

Clause 2

Authority for fixing compensation under Clause 2- SUPERINTENDING ENGINEER(C) / CHIEF ENGINEER(C), BSNL CIVIL ODISHA ZONE, BHUBANESWAR.

Clause 2 A

Whether Clause 2A shall be applicable

NO

Clause 3 A

Whether Clause 3A shall be applicable

NO

Clause 5

i) Time allowed for execution of work.

5 (Five) Months

ii) Authority to give fair and reasonable extension of time for completion of work.

Chief Engineer© /
Superintending Engineer©
BSNL Civil Odisha Zone
Bhubaneswar

Clause 6 A

Whether Clause 6 A shall be applicable

YES

Clause 7

Gross value of work to be done together with net payment / adjustment of advances for materials collected, if any, since the last such payment for being eligible to interim payment.

Contract Amount of Civil part
2xCompletion period in months.

Clause 10A

Reinforcement steel to be used in the work shall have to be procured as below :

TMT bars of 500 D OR 550 D
Produced by SAIL, TISCO,
JSPL,JSW Steel

Clause 10 C

Not applicable

Clause 10 CA

Applicable- For reinforcement the Index of Mild Steel- long products will be considered.

Clause 10 D

Not applicable

DNIT

Clause 11

Specification to be followed for execution of work.

CPWD Specifications Volume I & II 2009 with up to date correction slips as on the date of opening of the tender.

Clause 12

12.2 & 12.3 Limit for value of any item

50%(fifty percent)

Clause 16

Competent authority for deciding reduced rates.

Superintending Engineer(C)/
Chief Engineer (C),
BSNL Civil Odisha Zone,
Bhubaneswar

Clause 36(i)

Requirement of Technical Staff and rate of recovery in case of non-compliance shall be as per the following table:

Value of Work	Sl.No	Minimum qualification of Technical Representative	Discipline	Designation (Principal Technical/ Technical representative)	Minimum Experience in years	Number	Rate at which recovery shall be made from the contractor in the event of not fulfilling provision of clause 36(i)	
							figures	words
For Agreement amount upto Rs 150 lakhs	1	Graduate Engineer OR Diploma Engineer	Civil	Principal Technical representative	2 years for Graduate Engineer / 5 years for Diploma Engineer	1	Rs 15,000/-	Rs Fifteen Thousand only
For Agreement amount between Rs 150 lakhs to Rs 500 lakhs	1	Graduate Engineer	Civil	Principal Technical representative	5 years	1	Rs 25,000/-	Rs Twenty Five Thousand only
	2	Graduate Engineer OR Diploma Engineer	Civil	Technical representative	2 years for Graduate Engineer / 5 years for Diploma Engineer	1	Rs 15,000/-	Rs Fifteen Thousand only

Clause 37(i)

Extent of **GST** payable by **Contractor** for Building and Construction works

GST 12% Applicable. Any change in the rate of GST while making payment to the contractors will be adjusted accordingly.

DNIT

Clause 42

- i)
- (a) Schedule / statement for determining theoretical quantities of cement on the basis of Delhi Schedule of Rates printed by CPWD. Central Public Works Department, Delhi Schedule of rates 2016 for Delhi with upto date correction slips
- ii) **Variation permissible on theoretical quantities**
- a) Cement for works with estimated costs put to tender
- i) not more than Rs. 5 lakhs 3 % minus
- ii) more than 5 lakhs 2 % minus
- b) Steel reinforcement and structural steel sections for each diameter, section and category. 2 % minus

Star prices to be considered

Sl. No	Material	Star Price (Rate in Figures and Words)
1	For Cement	Rs.6400/-(Rupees Six Thousand Four Hundred)Only
2	For Reinforcement Steel conforming to BIS 1786 - TMT bars 500 D	Rs.57300/-(Rupees Fifty Seven Thousand Three Hundred)Only

The rate for recovery under clause 42 shall be same as the Star Price.

DNIT

SCHEDULE -D (for Civil work)

LIST OF PREFERRED MAKES FOR VARIOUS ITEMS OF WORK

The tenderer has to provide items specified as under or equivalent with the approval the Engineer-in-Charge for corresponding item of work.

MATERIAL	PREFERRED MAKE
Water Proofing Compound	Fosroc, Pidilite, Impermo, Sika, Accoproof, CICO
Admixtures in concrete	Fosroc, Sika, Pidilite, Roff
Grouting compound	Latticrete, Balandura, Fosroc
Epoxy grouts	Saint Gobin, Latticrete, Balandura, FOSROC
Non Metallic hardener compound	Fosroc, STP, Pidilite, CICO, FERROUS
Expoxy, Grouting Mortar	MBT, SIKA, STP, ENDURA, Dubond, Kerakoll, Don
CRCA frames	TATA, SAIL
Dash/Anchoring Fasteners	HILTI/Fischer, BOSCH
Nuts/Bolts & Screws	GKW/Atul
Flush door shutters	Kitply, Sitapur, Anandwood, Century, Greenply, Archid, Mayur
Hardware fittings	DORMA, EARL BIHAR, HETTICH, LAXMI, DOORSET, OZONE, EVERITE
Locks and Handles	Dorset, Godrej, Europa, Ozone, Everite, HETTICH, DORMA
Drawer multilock	KEYMAN/Earl Behari
Cylindrical lock	SECUR, DORSET, GODREJ
Mortice latch & lock	Godrej, Sheel
MS Tubes	Jindal, Tata, SAIL
Stainless steel sections	Jindal, Salem

DNIT

Glue	Fevicol,Vamicol,Pidilite,Dunlop
CP fittings & accessories	Parko,Kingston,Eso,Plumber,Crab tree,Jaguar,ROCA
Screws	Nettlefold/,GKW Ltd
Hydraulic door closer	Hardwyn, Dormia, Ozone, Yale, Everite,Godrej, Doorset
Welding Electrodes	Advani, ESAB India
Fire check wood doors	Godrej, Global, Radiant, Navair
Tinted film	Garware, Meditech, 3M
Privacy film	3M
PVC door shutter	Rajshri,Sintex,Duroplast
UPVC windows (with 10 yrs manufacters warranty)	Fenesta, Kommerlink, Veka, Reheau, Duroplast
Clear Glass/Reflective Glass	Saint Gobain, Modiguard, Asahi, Modifloat, Indor Asia
Patch fittings	DORMA,GEZE,OZONE
Silicon sealant	DOW Corning, GE, FERROUS
Laminated wooden flooring	KRONO, PERRO, HARO, BERRY, ARMSTRONG
PVC sheet flooring/Antistatic	LG, Armstong, Jindal, Wonderfloor
Paver block	Aeon,Hicon,Shan Fly Ash,Malu,Prathi,STAR Sai,Nitco,Gico,Ultra,EUROCON,UNISTONE
Ceramic tiles	,Kajaria,NITCO,Somany,Orient Bell, Oasis
Vitrified tiles/Polished Porcelain	,Kajaria,NITCO,EURO,Somany,Naveen
PVC Pipes and Fittings	Astral, Supreme, Finolex, Prince, Skipper, Ashirwad,Truebore
UPVC Pipes/fittings	Finolex, Supreme, Astral, SFMC
Insulation above false ceiling	Armaflex,Superior,Eurobatex

DNIT

Square perforated metal false ceiling	Conwed,Unimet,TRAC
Acoustical felt treatment	Soundtex
Exposed grid false ceiling	ARMSTRONG,NITTOBO,AMF,CELOTEX
Gypsum Board accessories	India Gypsum Ltd.
Calcium silicate Board false ceiling	Aerolite, Hylux, Armstrong, India Gypsum, Daikin, Decosmic
PVC water tank	Sintex(with ISI mark embosing only)
Mineral fibre false ceiling	Armstrong, AMF, USG, Saint Gobin
Blinds	Vista, Mac, Armstrong, Hunter Donglas
Furniture hardware	Unique, HATTICH, EBCO, Earl Behari
Aluminium sections	Hindalco, Jindal, Indal
Aluminium fittings	Everite, OXFORD, Argent, NLCO, Allans
Floor springs	Dorma, Ozone, Hardwyn, Yale, Everite, Godrej
Pre-laminated or plain particle board	Ecoboard, Asish, Novapan, Merino, Green, Century, Archid, Nepal Board
Aluminium composite panel (ACP)	Aludecor, Alponic, Alcobond, Alcopanel, Durabuilt, Alstrong
Polyvinyl Butyl film	Dupont, Trossifoil, Trussorf
Workstation and Modular furniture	Godrej, BPERGO, WIPRO, Herman, Durain, Miller, Featherlite
Plywood/Block Board	National,Green Ply,Kitply ,CENTURY, ALISHAN
Prelaminated MDF Board	Merino, ASIS, Century
HDF laminated boards	Armstrong, BVG, EGO floors, Square foot, Action Tera
Plain MDF Board	NUWOOD, Asis, Century
LAMINATES	Greenlam,Formica,Decolam,Merinolam, Century
Precast chequered cement concrete tiles	NITCO,Ultra,Aeons,Hicon,Gico,Unistone,Star

DNIT

Access flooring system (false floor)	Uitile,Donn
Perforated panels (false floor)	Uitile,Donn
Rodent repellent	MASER
Writing boards	Alkon,Whitemark,Writemark
Artificial leather	National leather Cloth Mfg Co., Bhor
Fabric Protection	Scotchguard of Birla 3M
Foam of chairs, Sofa	MM Foam, U FOAM
Fire retardant fabric	Trevira CS fabrics(Rajasthan Spinning & Weaving Mills Ltd.)
Ply Veneers	Green, Century
Polyrethan Sealant	Fosroc, Fesrons, Pidilite, MBT
Polythelene Board	Supreme, RV plast, Uriplast
Enamel Paints	Johnson & Nicholson,Asian,Royal touch ,Berger,ICI,Nerolac
Acrylic Distemper/Plastic Emulsion Paints	Asian Paints, ICI, Berger
Steel Primer	ICI, Asian Paints, Berger, Shalimar
Exterior paints	Snowcem India, Asian, ICI
Epoxy paint	Nerolac/Asian
Fire retardant paint	Firetard
Wood preservative	Bison by British paints, Woodguard,Termiseal
White cement	Birla White,JK White
Polyurethane Paint	MRF, ASIAN, Dulux, Bayev
Melamine Polish	Asian, Berger, ICI
Wax Polish	Reckitt & Colman

DNIT

PVC gratings	Prince, Prayag.
SW Pipes/Gully Traps	Perfect, Burn, Anand, RK, Hind, SKF, Crystal
CI Covers and frames	SKF, NECO, RIF, BC, NEER, BIC, KK, HEPSCO, KAJACO
SFRC Manhole covers	KK, SK., ADVENT
Stainless Steel Sink (Out of Salem Steel only)	Diamond, Nirali, Neekanth, Jayana, Prestige
Vitreous China Sanitary ware/Porcealin	Parryware, Cera, Hindware, Nycer
Plastic seat cover of W.C. (ISI mark only)	Commander, Hindware, Admiral
CPVC pipes and fittings	Ashrivad, Flowguard, Astral, Fusion
G. I. Pipes	Jindal (Hissar), Tata, Zenith, I.T.C., GST
G. I. Fittings	Unik, Zenith, HB
Gun metal valves	Leader, ZOLOTO, DRP
Float Valve	Viking, Prayag, Watertech
PPR Pipes and fittings	SFMC, Fusion, Supreme, Aashrivad
Gun Metal valves	Rolto, Leader, Sant, Caste
Water meters	Aquamet, Capstan, Kranti, Prima
CI valves	Zolto, Kirloskar, SANT, Kartar, Castle

ADDITIONAL CONDITIONS OF CONTRACT

The following “Additional conditions” shall be added to the standard conditions to take into account the special requirement of the work.

1. The intending tenderers shall note that the work is to be completed within the stipulated period.
2. The tenderers shall take into consideration the Drawings and Specifications and quote the rates accordingly. The quoted rates shall be inclusive of all charges such as Insurance, transportation, taxes fixed by the Central/State Government etc. Nothing extra shall be payable over the quoted rates.
3. In case of any discrepancy in the item given in the schedule of quantities appended with the tender and Architectural drawings relating to the relevant item, the contractor shall obtain clarifications in writing from the Engineer-in-Charge before execution.
4. The contractor shall take instructions from the Engineer-in-Charge for stacking of materials in any place. No excavated earth or building materials shall be stacked on areas where other buildings, roads, services of compound walls are to be constructed.
5. The surplus excavated earth which is beyond the requirement of the Government work may be allowed to be disposed off by the contractor on his own or to sell the surplus earth to private parties at his discretion, but nothing extra shall be paid for carriage of disposal of surplus earth, if the same is not required for any other Government work. The approval of the Engineer-in-Charge in writing is required to be obtained for the above.
6. The structural drawings for the work shall be issued in stages taking into consideration the approved programme as well as the actual progress.
7. The manufactured materials used on the work shall have ISI mark. In case of materials for which no manufacture has been licensed to manufacture, the materials with ISI marking, the material shall conform to the provision of the CPWD specifications. In the case of non-ISI marked materials, tests shall be conducted to ensure that they conform to the specifications or codes mentioned above. BIS marked materials may also be got tested if felt necessary by the Engineer-in-Charge.
9. All materials for which testing is mandatory before being allowed for incorporation in the work shall be purchased well in advance of their actual requirement in the work at site, so as to afford enough availability of time for getting the material tested and obtaining the approval of the Engineer-in-Charge.
9. Other agencies doing works related with this project will also simultaneously execute the works and the contractor shall afford necessary facilities for the same. The contractor shall leave such necessary holes, openings etc. for laying / burying in the work of pipes, cables, conduits, clamps, boxes and hooks for fan clamps etc. as may be required for other agencies, conduits for electrical wiring / cables will be laid in a way that they leave enough space for concreting and do not adversely affect the structural members. Nothing extra over the agreement rates shall be paid for the same.
10. Royalty, if any, at the prevalent rates shall have to be paid by the contractor on all the boulders, metals, shingle, sand and bajri etc. collected by him for

- the execution of the work direct to the Revenue authority or authorized agent of the State Government concerned or Central Government.
11. The rates quoted shall include all taxes, royalty, seignior age charges that are applicable from time to time as per statutory rules of State / Central Government.
 12. The contractor shall make his own arrangements for obtaining electric / water connections, if required, and make necessary payments directly to the Department concerned.
 13. The work shall be carried out in a manner complying in all respects with the requirements of relevant byelaws of the Municipal Committee / Municipal Corporation / Development Authority / Improvement Trust under the jurisdiction of which the work is to be executed or as directed by the Engineer-in-Charge and nothing extra shall be paid on this account.
 14. The contractor shall provide at his own cost suitable weighing and measuring arrangements at site for checking the weight / dimensions as may be necessary for execution of the work.
 15. No compensation / payment shall be payable to the contractor for any damage caused by rains, snow fall, lightning, wind, storm, floods tornadoes, earthquakes or other natural calamities during execution of work. He will make good all such damages at his own cost and no claim on this account will be entertained.
 16. Some restrictions may be imposed for regulating the construction/work activities, storage of materials, entry and movement of the personal/workers for security reasons by the competent security in-charge or by the Engineer-in-Charge or his representative and in such case the contractor shall be bound to follow all such restriction/instructions and nothing extra shall be payable on this account.
 17. All cement bags and all other similar perishable items shall be stored by the contractor in a separate go-down which shall be exclusively constructed by the contractor for this purpose at his own cost as per general guidelines given in the “ Typical Sketch for :-
Cement Godown” under clause 3.2.1.4 of the Specifications. The dimensions given in the said sketch are only indicative and the contractor shall be bound to construct the storage godown of sufficient size so as to properly store the appropriate quantity of cement required for consumption for not less than ONE MONTH. Such go-down shall have weather proof roof and walls. The go-down shall be provided with a single door with arrangement for locking it simultaneously with two locks. The contractor shall be fully responsible for the safe custody of all the materials even if the materials are kept and stored under double lock system. The account of daily receipts and issues of the cement bags shall be maintained in the said register which shall be signed daily by the contractor or by his authorized agent in token of correctness of the entries.
 18. The contractor shall also be bound to observe and follow all the provisions of “The Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act 1996” and “The Building and other Construction Workers Welfare Cess Act 1996” and all the rules framed there-under. Nothing extra on this account shall be paid to the contractor.

19. Any cement slurry added over a base surface or for continuation of concreting for better bond is added to have been built in the item unless otherwise specified and nothing extra shall be payable or extra cement considered with consumption on this account. Rates of all items in which use of cement is involved shall be inclusive of curing.
20. Unless otherwise specified in the Schedule of quantities of items, the rate for all items of the work shall be inclusive of pumping out or bailing out water encountered from any sources such as rain, sub-soil water, flood or any other causes whatsoever. The foundation pits, trenches etc. shall be kept free from water while the works below ground level are in progress. Nothing extra on this account shall be payable to the contractor.
21. Unless otherwise provided in the schedule of quantities of item of work, the rates tendered by the contractor shall be for all heights, lifts and leads and depth of the building and nothing extra shall be payable to the contractor on this account.
22. Portland Pozzolona Cement (flyash blended) conforming to IS: 1489(Part 1) shall be used in the work. The certificate from PPC manufacturer indicating the percentage of flyash shall be submitted to the Engineer-in-charge before using the cement in the work. Hence, the tenderers may quote their rates for the items requiring cement considering the rate of PPC.

ADDITIONAL CONDITIONS (GENERAL)

(Para 3.1 to Para 3.2.6 (in pages 102 to pages 104) under Additional conditions in BSNL booklet on General conditions of contract for building works may be treated as deleted)

1.0 CEMENT

- 1.1 The contractor shall procure Portland Pozzalona Cement (conforming to IS:1489-Part 1) as required in the work, from reputed manufacturers of cement having a production capacity of one million tonnes or more per annum such as ACC, Ultratech, ZUARI, Birla and Cement Corporation of India, Gujarat Ambuja etc., as approved by the Ministry of Industry , Government of India and holding license to use ISI certification mark for their product. The tenderers may also submit a list of names of cement manufacturers which they propose to use in the work. The tender accepting authority reserves right to accept or reject name(s) of cement manufacturer(s) which the tenderer proposes to use in the work. No change in the tendered rates will be accepted if the tender accepting authority does not accept the list of cement manufacturers, given by the tenderer, fully or partially. Supply of cement shall be taken in 50 kg bags bearing manufacturer's name and ISI marking. Samples from cement arranged by the contractor shall be taken by the Engineer-in-Charge and got tested in accordance with provisions of relevant BIS codes. In case test results indicate that the cement arranged by the contractor does not conform to the relevant BIS codes, the same shall stand rejected and shall be removed from the site by the contractor at his own cost within a week's time of written order from the Engineer-in-Charge to do so.
- 1.2 The cement shall be brought at site in bulk supply of approximately 10 tonnes or as decided by the Engineer-in-Charge.
- 1.3 The cement godown of the capacity to store a minimum of 200 bags of cement shall be constructed by the contractor at site of work for which no extra payment shall be made. Double lock provision shall be made to the door of cement godown. The keys of one lock shall remain with Engineer-in-Charge or his authorized representative and keys of the other lock shall remain with the contractor. The contractor shall be responsible for the watch and ward and safety of the cement godown. The contractor shall facilitate the inspection of the cement godown by the Engineer-in-Charge or his authorized representatives.
- 1.4 The cement shall be got tested by the Engineer-in-Charge and shall be used on the work only after satisfactory test results have been received. The contractor shall supply free of charge the cement required for testing including its transportation cost to testing laboratories. The frequency and details of the tests shall be decided by the Engineer- in-Charge depending on the quantum of supply in each batch. The cost of tests shall be borne by the contractor / Department in the manner indicated below:
 - (a) By contractor, if results show that the cement does not conform to the relevant BIS codes.

- (b) By Department, if results show that the cement conforms to relevant BIS codes.
- 1.5 The actual issue and consumption of cement on work shall be regulated and proper accounts maintained as provided in clause 10 of the contract. The theoretical consumption of cement shall be worked out as per procedure prescribed in clause 42 of the contract and shall be governed by the conditions laid therein. In case the cement consumption is less than theoretical consumption including permissible variation, recovery at rate so prescribed shall be made. In case of excess consumption no adjustment shall be made.
 - 1.6 Cement brought to site and cement remaining unused after completion of work shall not be removed from site without written permission of the Engineer-in-charge.
 - 1.7 Damaged cement shall be removed from the site immediately by the contractor on receipt of a notice in writing from the Engineer-in-charge. If he does not do so within 3 days of receipt of such notice, the Engineer-in-charge shall get it removed at the cost of the contractor.
 - 1.8 The cement bags shall be stacked on proper floors consisting of two layers of dry bricks laid on well consolidated earth at a level of at least one foot above ground. The stacks shall be in rows of 2 and 10 bags high with minimum of 0.6m clear. Bags should be placed horizontally continuous in each line. Actual size / shape of go down shall be as per site requirement and nothing extra shall be paid on this account. The decision of Engineer-in-charge regarding capacity shall be final.
 - 1.9 Cement register for the cement shall be maintained at site. The account of daily receipts and issues of cement shall be maintained in the register in the proforma prescribed and signed daily by contractor or his authorized agent.
 - 1.10 A Certificate from the manufacturer indicating the percentage of Fly ash in each batch of cement shall be obtained and submitted to the Engineer-in-charge for his approval when PPC is proposed to be used in work. PPC shall be permitted only after prior approval of Engineer-in-charge.

2.0 STEEL

- 2.1 The contractor shall procure TMT bars of Fe 500D or 550D grade from SAIL, TISCO or RINL or JSPL or JSW Steel . The TMT bars procured shall conform to manufacturer's specifications. The specifications of TMT bars procured shall meet the provisions of IS 1786: 2008 pertaining to Fe 500D / 550D grade of steel.
- 2.2 The contractor shall have to obtain and furnish test certificates to the Engineer-in-charge in respect of all supplies of steel brought by him to the site of work.
- 2.3 Samples shall also be taken and got tested by the Engineer-in-charge as per the provisions in this regard in relevant BIS codes. In case the test results

indicate that the steel arranged by the contractor does not conform to the specifications as defined under para 2.1 above, the same shall stand rejected, and it shall be removed from the site of work by the contractor at his cost within a week's time of written orders from the Engineer-in-charge to do so.

- 2.4 The steel reinforcement bars shall be brought to the site in bulk supply as decided by the Engineer-in-Charge.
- 2.5 The steel reinforcement shall be stored by the contractor at site of work in such a way as to prevent distortion and corrosion, and nothing extra shall be paid on this account. Bars of different sizes and lengths shall be stored separately to facilitate easy counting and checking.
- 2.6 For checking nominal mass, tensile strength, bend test, re-bend test, etc., specimen of sufficient length shall be cut from each size of the bar at random, and at frequency not less than that specified below:-

Size of bar	For consignment below 100 tonnes	For consignment over 100 Tonnes
Under 10mm dia	One sample for each 25 tonnes or part thereof	One sample for each 40 tonnes or part thereof
10 mm to 16mm dia	One sample for each 35 tonnes or part thereof	One sample for each 45 tonnes or part thereof
Over 16 mm dia	One sample for each 45tonnes or part thereof	One sample for each 50 tonnes or part thereof

- 2.7 The contractor shall supply free of charge the steel required for testing including its transportation to testing laboratories. The cost of tests shall be borne by the contractor / Department in the manner indicated below:
- By the contractor, if the results show that the steel does not conform to relevant BIS codes.
 - By the Department, if the results show that the steel conforms to relevant BIS codes.
- 2.8 The actual issue and consumption of steel on work shall be regulated and proper accounts shall be maintained as provided in clause 10 of the contract. The theoretical consumption of steel shall be worked out as per procedure prescribed in clause 42 of the contract and shall be governed by conditions laid therein. In case the consumption is less than theoretical consumption including permissible variations, recovery at the rate so prescribed shall be made. In case of excess consumption, no adjustment needs to be made.
- 2.9 The steel brought to site and steel remaining unused shall not be removed from site without the written permission of the Engineer-in-Charge.
- 2.10 The contractor shall furnish to BSNL all the purchase invoices for cement and Steel for every consignment.

3.0 INSPECTION OF SITE

The Contractors are advised to inspect and examine the site and its surroundings and satisfy themselves with the nature of site, the means of access to the site, the constraints of space for stacking material / machinery, labour etc. constraints put by local regulations, if any, weather conditions at site, general ground / subsoil conditions etc. or any other circumstances which may affect or influence their tenders. The site is available for work. The contractor shall, immediately on issue of letter of acceptance of tender, make arrangements for starting the work.

4.0 The Contractor shall, if required by him, before submission of the tender, inspect the drawings in the Office of the Engineer-in-Charge. The Department shall not bear any responsibility for the lack of knowledge and also the consequences, thereof to the Contractor. The information and data shown in the drawings and mentioned in the tender documents have been furnished, in good faith, for general information and guidance only. The Engineer-in-Charge, in no case, shall be held responsible for the accuracy thereof and / or interpretations or conclusions drawn there from by the Contractor and all consequences shall be borne by the Contractor. No claim, whatsoever, shall be entertained from the Contractor, if the data or information furnished in tender document is different or in-correct otherwise, or actual working drawings are at variance with the drawings available for inspection or attached to the tender documents. It is presumed that the Contractor shall satisfy himself for all possible contingencies, incidental charges, wastages, bottlenecks etc. likely during execution of work and acts of coordination, which may be required between different agencies. Nothing extra shall be payable on this account.

5.0 The nomenclature of the items given in the schedule of quantities gives in general the work content but is not exhaustive i.e. does not mention all the incidental works required to be carried out for complete execution of the item of work. The work shall be carried out, all in accordance with true intent and meaning of the specifications and the drawings taken together, regardless of whether the same may or may not be particularly shown on the drawings and / or described in the specifications, provided that the same can be reasonably inferred there from.

6.0 Before tendering for the work, the contractor shall visit the site and assess the manner in which he is able to arrange the facilities required for work. The contractor will not be permitted to erect labour huts in CPRI site. He shall make his own arrangements for stores, field office etc. Material go-down, site office etc required for the work and constructed by him should be dismantled and removed from the site soon after completion of work. The Engineer-in-Charge shall in no way be responsible for any delay on this account and no claim, whatsoever, on this account shall be entertained. Nothing extra shall be payable on this account.

7.0 All ancillary and incidental facilities required for execution of work like, stores, fabrication yard, offices for Contractor, watch and ward, temporary ramp required to be made for working at the basement level, temporary structure

for plants and machineries, water storage tanks, telephone, etc. required for execution of the work, liaison and pursuing for obtaining various No Objection Certificates, completion certificates from local bodies etc., protection works, barricading, testing facilities / laboratory at site of work, facilities for all field tests and for taking samples etc. during execution or any other activity which is necessary (for execution of work and as directed by Engineer-in-Charge), shall be deemed to be included in rates quoted by the Contractor, for various items in the schedule of quantities unless otherwise specified. Nothing extra shall be payable on this account.

8.0 SUBMISSIONS AFTER AWARD OF WORK

The Contractor shall submit the following details after award of work:

- a. List of Equipments proposed to be deployed for this work is to be mandatorily provided and deployed by the contractor.
- b. Site organization chart with Bio-data of Site Engineer and Key Personnel proposed to be deployed at site.
- c. The details of shuttering material proposed to be used to complete the entire R.C.C/ structural steel work commensurate with overall stipulated period for completion of work.
- d. The contractor shall prepare and submit a tentative integrated Bar Chart (for Civil and E & M services) clearly indicating the various activities, in a manner to complete the entire work covered under this tender within the stipulated period and as per milestones.

9.0 The Contractor shall keep himself fully informed of all acts and laws of the Central & State Governments, all orders, decrees of statutory bodies, tribunals having any jurisdiction or authority, which in any manner may affect those engaged or employed and anything related to carrying out the work. All the rules & regulations and bye-laws laid down by any statutory bodies shall be adhered to, by the contractor, during the execution of work. The Contractor shall also adhere to all traffic restrictions notified by the local authorities. The water charges (for municipal water connection as well as tanker water) shall be borne by the contractor. Also, if the contractor obtains water connection for the drinking purposes from the municipal authorities or any other statutory body, the consequent sewerage charges shall be borne by the contractor. He shall protect and indemnify BSNL and its officials & employees against any claim and /or liability arising out of violations of any such laws, ordinances, orders, decrees, by himself or by his employees or his authorized representatives. Nothing extra shall be payable on these accounts.

10.0 Royalty at the prevalent rates shall be paid by the Contractor or the RMC supplier as per the terms of supply between them on all materials such as boulders, metals, sand and bajri etc. collected by him for the execution of the work, directly to the revenue authority of the state government concerned. Nothing extra shall be payable on this account.

11.0 The Contractor shall assume all liability, financial or otherwise in connection with this contract and shall protect and indemnify BSNL from any and all damages and claims that may arise on any account. The

contractor shall indemnify BSNL against all claims in respect of patent rights, royalties, design, trademarks of name or other protected rights, damages to adjacent buildings, roads or members of public, in course of execution of work or any other reasons whatsoever, and shall himself defend all actions arising from such claims and shall indemnify BSNL in all respects from such actions, costs and expenses. Nothing extra shall be payable on this account.

12.0 SIGN BOARDS

The Contractor shall provide and erect a display board of size and shape as required and paint over it, in a legible and workman like manner, the details about the salient features of the project, as required by the Engineer-in-Charge. The Contractor shall fabricate and put up a sign board in an approved location and to an approved design indicating name of the project, client / owner, etc. Nothing extra shall be payable on this account.

13.0 FACILITIES FOR SITE OFFICE

The Contractor shall provide, construct and maintain at all times during execution and till the completion of work, a temporary site office with adequate electric light fittings, fans, electric/ power points, switches etc for use of the Engineer- in-Charge and his authorized representatives. Such office shall be provided with suitable partitions, doors, windows, locking arrangement and water and electricity facility. The entire site office and its surroundings shall be maintained in a neat and clean condition by the Contractor for the entire duration of the construction. The premises / facilities provided by the contractor shall be demolished/ dismantled / disconnected and material carted away by him at his own cost after the completion of work or as directed by Engineer-in-Charge. The rates quoted by the Contractor shall be inclusive of providing and maintaining such facilities and nothing extra shall be payable on this account.

14.0 SPECIALIZED AGENCIES:

14.1 The tenderer shall submit list of Specialized Agencies for the specified items of the Civil work for executing the work and furnish the name of Specialized Agencies for each of the various works.

14.2 The Contractor shall obtain prior approval from the Engineer-in-charge before placing order for any specific material or engaging any specialized agencies. The Contractor shall make a detailed submittal with catalogues and highlighted proposed specifications. A list of works executed by the specialized agency, is to be furnished to the Engineer-in-charge, for seeking prior approval. The specialized agency should have successfully completed at least one work of similar nature.

14.3 Save in exceptional circumstances, the main contractor shall not change the specialized agency. However, if the change is warranted, he may do so with the approval of Engineer-in-Charge. This shall however be without

any change in the accepted rates of the contract agreement and without any cost implications to the Department.

15.0 PROTECTIVE / SAFETY MEASURES

Necessary protective and safety equipment shall be provided to the Site Engineer, workers & Supervisory staff by the Contractor at his own cost and used at site.

16.0 The Contractor shall do proper sequencing of the various activities by suitably staggering the activities within various pockets in the plot so as to achieve early completion. The agency may deploy adequate equipment, machinery and labour as required for the completion of the entire work within the stipulated period specified. Adequate number/sets of equipment in working condition, along with adequate stand-by arrangements, shall be deployed during entire construction period. It shall be ensured by the Contractor that all the equipment, Tools & Plants, machineries etc provided by him are maintained in proper working conditions at all times during the progress of the work and till the completion of the work. Further, all the constructional tools, plants, equipment and machineries provided by the Contractor, on site of work or his work shop for this work, shall be exclusively intended for use in the construction of this work and they shall not be shifted / removed from site without the permission of the Engineer-in-Charge.

17.0 Use of Personal protective Equipment and safety devices relevant to site activities shall be arranged by the contractor or as directed by Engineer-in-Charge and the cost on this account shall be deemed to be included in rates quoted by the Contractor, for various items in the schedule of quantities. Nothing extra shall be payable on these accounts

The stacking of materials on the access points should be avoided so as to facilitate the movement of the workmen. Proper illumination in the access area will be also ensured. Suitable platforms are to be provided before allowing any workmen to work at height. The openings are to be strictly avoided in the working platforms to avoid fall of person & materials from Heights. All scaffolds must be satisfying specified standards and it should be checked before erection of the same at site. Throwing the scaffold materials from height is to be avoided.

Safety nets shall be used to arrest the falling of the construction material and debris. The size of the safety net shall be as per site requirement. Any opening, hole or gap on floors, grating or walking / working surface, where person, tools or materials can be subject to potential fall, shall be appropriately covered and / or guarded. Covers when applied shall be of substantial strength. Where scaffold planks are used as cover, they must be properly held together to act as one cover assembly. Guard rails shall be made of solid materials (i.e. scaffold tubing) and shall be capable to sustain load without failure.

Multilevel working at same places (i.e. work within shafts, floor edges) one above the other shall not be permitted. Proper protection with safety nets & PPE shall be provided prior to allowing some critical multilevel working. The erection jobs shall be performed only under the supervision of competent

personnel. The transport of construction material/ debris to/from work site shall be done during lean hours of the day and necessary supervision shall be ensured to prevent any untoward instances. The area of erection shall be cordoned off and Danger signage's shall be displayed. Nothing extra shall be paid for the above and the cost on this account shall be deemed to be included in rates quoted by the Contractor, for various items in the schedule of quantities. The work shall be so planned so as to provide temporary approach for vehicular movement to the occupants of the building at all times. If required, a diversion shall be provided for access to the building.

18.0 DISPLAY PERMISSIONS

The Contractor shall display all permissions, licenses, registration certificates, bar charts, other statements etc under various labour laws and other regulations applicable to the works, at his site office.

19.0 REMOVAL OF CONSTRUCTION DEBRIS ETC. FROM SITE

The Contractor shall not stack building material / construction debris / muck on the land or road of the local development authority or on the land owned by the client, as the case may be. So the muck, rubbish etc. shall be removed periodically as directed by the Engineer-in- Charge, from the site of work to the approved dumping grounds as per the local byelaws and regulations of the concerned authorities and all necessary permissions in this regard from the local bodies shall be obtained by the Contractor. Nothing extra shall be payable on this account unless otherwise specified. In case, the Contractor is found stacking the building material / debris as stated above, the Contractor shall be liable to pay the stacking charges / penalty as may be levied by the local body or any other authority and also to face penal action as per the rules, regulations and bye-laws of such body or authority. The Engineer –in-Charge shall be at liberty to recover, such sums due but not paid to the concerned authorities on the above counts, from any sums due to the Contractor including amount of the Security Deposit and performance guarantee in respect of this contract agreement.

20.0 TOOLS AND PLANTS

No tools and plants including any special T&P etc. shall be supplied by the Department and the Contractor shall have to make his own arrangements at his own cost. No claim of hindrance (or any other claim) shall be entertained on this account

21.0 COORDINATION WITH OTHER AGENCIES

The Contractor shall conduct his work so as not to interfere with or hinder the progress of the work being performed by other Contractors or by the Engineer-in-Charge. As far as possible, he shall arrange his work and place, so as not to interfere with the operations of other Contractors or shall arrange his work with that of the others, in an acceptable and coordinated manner and shall perform it in proper sequence.

22.0 FACILITIES BY THE CONTRACTOR TO THE OTHER CONTRACTORS / AGENCIES

The Contractor shall cooperate with and provide the facilities to other agencies working at site for smooth execution of the work. The Contractor shall :

- a. Properly co-ordinate their work with the work of other Contractors.
- b. Provide control lines and benchmarks to other Contractors.
- c. Co-ordinate with other Contractors for leaving inserts, making chases, alignment of services etc. at site.
- d. Adjust work schedule and site activities in consultation with the Engineer-in-Charge and other Contractors to suit the overall schedule completion.
- e. Resolve the disputes with other Contractor amicably and the Engineer-in-Charge shall not be made intermediary or arbitrator. The contractor shall indemnify the Department against any claim(s) arising out of such disputes.

23.0 The site of work shall be always kept clean due to constraints of space and to avoid any nuisance to the users of buildings in the adjacent plots. The Contractor shall take all care to prevent any water- logging at site. The wastewater, slush etc. shall not be allowed to be collected at site. It may be directly pumped into nearby drains with prior approval of the concerned authorities. For discharge into public drainage system, necessary permission shall be obtained from relevant authorities after paying the necessary charges, if any, directly to the authorities. The work shall be carried out in such a way that the area is kept clean and tidy. All the fees/charges in this regard shall be borne by the Contractor. Nothing extra shall be payable on this account.

24.0 PREVENTION OF NUISANCE AND POLLUTION

The Contractor shall take all necessary precautions to prevent any nuisance or inconvenience to the owners, tenants or occupants of the adjacent properties and to the public in general. The Contractor shall take all care, as not to damage any other adjacent property or other services running adjacent to the plot. If any damage is done, the same shall be made good by the Contractor at his own cost and to the entire satisfaction of the Engineer-in-Charge. The Contractor shall use such methodology and equipment for execution of the work, so as to cause minimum environmental pollution of any kind during construction, to have minimum construction time and minimum inconvenience to road users and to the occupants of the buildings on the adjacent plot and public in general, etc. He shall make good at his own cost and to the entire satisfaction of the Engineer in Charge any damage to roads, paths, cross drainage works or public or private property whatsoever caused, due to the execution of the work or by traffic brought thereon, by the Contractor. Further, the Contractor shall take all precautions to prevent any pollution of streams and waterways. All waste or superfluous

materials shall be carted away by the Contractor, entirely to the satisfaction of the Engineer-in-Charge. Utmost care shall be taken to keep the noise level to the barest minimum so that no disturbance as far as possible is caused to the occupants/ users of adjoining buildings. No claim what so ever on account of site constraints mentioned above or any other site constraints not specifically stated here, shall be entertained from the Contractor. Therefore, the Contractors are advised to visit site and get first hand information of site constraints. Accordingly, they should quote their tenders. Nothing extra shall be payable on this account.

25.0 SCAFFOLDING

Wherever required for the execution of work, all the scaffolding shall be provided and suitably fixed, by the Contractor. It shall be suitably braced for stability, with all the accessories, gangways, etc. with adjustable suitable working platforms to access the areas with ease for working and inspection. It shall be designed to take all incidental loads. It should cater to the safety features for workmen. It shall be ensured that no damage is caused to any structure due to the scaffolding. Charges for Double scaffolding shall be payable under relevant agreement item.

26.0 The Contractor shall maintain all the work in good condition till the completion of entire work. The Contractor shall be responsible for and shall make good, all damages and repairs, rendered necessary due to fire, rain, traffic, floods or any other causes. The Engineer-in-Charge shall not be responsible for any claims for injuries to person/workmen or for structural damage to property happening from any neglect, default, want of proper care or misconduct on the part of the Contractor or of any other of his representatives, in his employment during the execution of the work. The compensation, if any, shall be paid directly to the Department / authority / persons concerned, by the Contractor at his own cost.

27.0 For completing the work in time, the Contractor might be required to work in two or more shifts (including night shifts). No claim whatsoever shall be entertained on this account, notwithstanding the fact that the Contractor may have to pay extra amounts for any reason, to the labourers and other staff engaged directly or indirectly on the work according to the provisions of the labour and other statutory bodies regulations and the agreement entered upon by the Contractor with them.

28.0 In case of flooding of site on account of rain or any other cause and any consequent damage, whatsoever, no claim financially or otherwise shall be entertained notwithstanding any other provisions elsewhere in the contract agreement. Also, the Contractor shall make good, at his own cost, the damages caused, if any.

29.0 The Contractor shall make all necessary arrangements for protecting from rains, the work already executed and for carrying out the further work, during monsoon including providing and fixing temporary shelters, protections etc. Nothing extra shall be payable on this account.

30.0 SECURITY & TRAFFIC ARRANGEMENTS

In event of any restriction being imposed by the Department, traffic or any other statutory authority having control over the project, on the working or movement of labour, materials, etc., the Contractor shall strictly follow all such restrictions or instructions issued regarding the same and nothing extra shall be payable to the Contractor on account of such restrictions or instructions.

31.0 STORAGE OF MATERIAL AT SITE

No inflammable materials including P.O.L shall be allowed to be stored in huge quantity at site. Only limited quantity of P.O.L may be allowed to be stored at site subject to the compliance of all rules/instructions issued by the relevant authorities and as per the direction of Engineer-in-Charge in this regard. Also all precautions and safety measures shall be taken by the Contractor for safe handling of the P.O.L products stored at site. All consequences on account of unsafe handling of P.O.L shall be borne by the Contractor.

32.0 NO WAIVING OF LEGAL RIGHTS AND POWERS

The Engineer-in-Charge shall not be precluded or stopped from taking any measurements, and framing of estimates or detaining any certificates made either before or after the completion and acceptance of the work and payment, from showing the true amount and character of the works performed and materials furnished by the Contractor and from showing that any such measurements, estimates or certificates untrue or incorrectly made and that Engineer-in-Charge shall not be precluded or stopped from recovering from the Contractor such damages as it may be sustained by reasons of his failure to comply with the terms and conditions of the contract.

33.0 FINAL TESTING OF THE INSTALLATION

The Contractor shall demonstrate trouble free functioning of all the Civil and E & M installations and services. The Engineer-in-Charge or his authorized representatives shall carry out final inspection of the various Civil and E & M services and installations. Any defect(s) noticed during demonstration shall be rectified by the Contractor at his own cost to the entire satisfaction of the Engineer-in-Charge. Nothing extra shall be payable on this account.

34.0 No claim for idle establishment & labour, machinery & equipments, tools & plants and the like, for any reason whatsoever, shall be admissible during the execution of work as well as after its completion.

35.0 PLUMBING WORK.

The contractor shall employ the specialized agency for executing of plumbing work with the prior approval of Engineer – in – Charge.

36.0 COMPUTERIZED MEASUREMENTS AND BILLING

- a) The measurements shall be recorded and entered in computerised format in the first instance by the contractor, and a hard copy shall be submitted to the BSNL.
- b) These measurements shall be got checked by the Junior Telecom Officer / Sub Divisional Engineer/Executive Engineer. The contractor shall incorporate all such changes or corrections, as may be done during these checks, to their draft computerised measurements, and submit to the BSNL the corrected computerized measurements in the form of a book, duly hard bound in red colour, and with its pages duly numbered.
- c) The Computerised Measurement Book shall be allotted a serial number by BSNL.
- d) The Computerized Measurement Book given by the contractor, duly bound, with its pages duly numbered, shall have no cutting or overwriting.
- e) In case of any error, the Computerised Measurement Book shall be cancelled, and the contractor shall resubmit a fresh Computerized Measurement Book. This should be done before the corresponding computerised bill is submitted to the BSNL for payment.
- f) The contractor shall submit as many copies of Computerised Measurement Books as may be required for the purpose of reference and record in the various offices of the BSNL.
- g) Nothing extra shall be paid on the above account.

CONDITIONS FOR OTHER TAXES AND ROYALTIES

1. **The rates offered should be inclusive of GST liable to be paid by contractors(either directly payable by them or through BSNL .GST rate is mentioned under clause 37(i) in the schedule F. Any increase in the rate of GST while making payment of bills will be compensated to the contractor. Any decrease in the rate of GST while making payment of bills will be recovered from the bills of contractor .Contribution towards EPF, ESIC and all other taxes as applicable. Insurance, loading, unloading, transportation etc should be included on the quoted rates. The rate shall be firm & final.**
2. **Income Tax and surcharges** over Income Tax etc. at the rates fixed by the Ministry of Finance. Government of India shall be deducted from all the running and final bills of the contractor. Should there be any increase in rate of Income Tax and surcharge during execution of the contract, the same shall be payable by the contractor
3. **Cost for the welfare of construction workers shall also be deducted from the bills of the contractors.**
4. **Royalty** shall have to be paid by the contractor on all materials such as stone, bricks, boulders, metal, shingle, bajri, stone aggregate, coarse sand and fine sand etc. or any other materials used for the execution of the work direct to the Revenue Authority of the District/ State Govt. concerned.

SCHEDULE -A (for Civil work)

SCHEDULE OF QUANTITIES					
Name of the work : Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park,Nandankanan, Bhubaneswar.					
I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount(Rs)
Sub-Head : Earth Work					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
a)	All kinds of soil.	20.00	Cum		
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	50.00	Cum		
Sub-Head : Concrete Work					
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
a)	1:5:10 (1 cement : 5 coarse sand(zone-III) : 10 graded stone aggregate 40 mm nominal size)	12.00	Cum		
Sub-Head : Reinforced Cement Concrete					
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
a)	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	118.00	Cum		

DNIT

5	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :				
a)	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	5.00	Cum		
6	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	10.00	Cum		
7	Centering and shuttering including strutting, propping etc. and removal of form for :				
a)	Foundations, footings, bases of columns, etc. for mass concrete.	50.00	Sqm		
b)	Suspended floors, roofs, landings, balconies and access platform.	390.00	Sqm		
c)	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	530.00	Sqm		
d)	Columns, Pillars, Piers, Abutments, Posts and Struts.	165.00	Sqm		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level.				
a)	Thermo-Mechanically Treated bars of grade Fe-500 D or more.	12700.00	Kg		
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
a)	Thermo-Mechanically Treated bars of grade Fe-500 D or more.	2000.00	Kg		

DNIT

10	Smooth finishing of the exposed surface of R.C.C. work with 6 mm thick cement mortar 1:3 (1 Cement : 3 fine sand)	820.00	Sqm		
11	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	80.00	metre		
Sub-Head : Brick Work					
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
a)	Cement mortar 1:6 (1 cement : 6 coarse sand)	6.00	Cum		
13	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 7.5 average compressive strength in super structure above plinth level up to floor V level in :				
a)	Cement mortar 1:6 (1 cement : 6 coarse sand)	35.00	Cum		
Sub-Head : Steel Work					
14	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
a)	Hot finished welded type tubes.	11000.00	Kg		
15.	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
a)	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	300.00	Kg		
16	Providing and fixing bolts including nuts and washers complete.	65.00	Kg		
Sub-Head : Flooring					
17	Cement concrete pavement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including finishing complete.	4.00	Cum		
Sub-Head : Roofing					

18	Providing and fixing precoated Galvalume profile sheets of TATA, JSW or equivalent make manufactured from Zinc / Aluminium alloy coated (55% Aluminium , 43.50% Zinc and 1.50% Silicon) high tensile steel (Size, Shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm (+0.50%), total coated thickness required colours (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %), total coated thickness with zinc coating not less than 70 gm per sqm in 5510 mpa steel grade. The sheet shall be fixed using self drilling / self tapping screws of size (5.5 X 55mm) with EPDM seal, complete upto any pitch in Horizontal / Vertical or curved surfaces excluding the cost of purlins, rafters and including cutting to size and shape wherever required.	560.00	Sqm		
19	Providing and fixing precoated galvalume profile sheets accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating not less than 70 gm per sqm in 550 mpa steel grade, using self drilling/ self tapping screws complete :				
a)	Plain ridge 600 mm	32.00	metre		
	Sub-Head : Finishing				
20	12 mm cement plaster of mix :				
a)	1:6 (1 cement: 6 coarse sand)	160.00	Sqm		
21	15 mm cement plaster on rough side of single or half brick wall of mix :				
a)	1:6 (1 cement: 6 coarse sand)	140.00	Sqm		
22	Finishing walls with Acrylic Smooth exterior paint of required shade :				
a)	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	300.00	Sqm		
23	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
a)	Two or more coats on new work.	550.00	Sqm		
	Sub-Head : Dismantling and Demolishing				

24	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	4.00	Cum		
25	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	20.00	Cum		
	Sub-Head : Pile Work				
26	Boring, providing and installation bored cast-in-situ reinforced cement concrete piles of 1:1.5:3 (1cement:1.5 sand:3 graded stone agtt. of 20mm nominal size) of specified diameter and length below the pile cap, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. by percussion drilling using Direct mud circulation (DMC) or Bailer and chisel technique by tripod and mechanical Winch Machine all complete, including removal of excavated earth with all its lifts and leads (length of pile for payment shall be measured up to bottom of pile cap).				
	Note: Truck Mounted rotary/TMR/Tubewell boring machine shall not be used.				
a)	380 mm dia piles	200.00	metre		
	Sub Head-Miscllaneous				

27	Providing and laying textured industrial tile of size 300x300x12 mm having water absorption less than 0.5% and conforming to IS: 4457:2007 of approved make in all colours and shades in outdoor floors such as footpath, court yard, parking areas, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	460.00	Sqm		
28	Making temporary arrangement of water retaining structure about a height of 2.00 meter with placing stiched sand bags in a stacked manner or by any other means to make a barrier to prevent water leakage inside the specified area of about 40mtrx 20 mtr for carrying out the construction work all complete. Rate is inclusive of carriage, loading/unloading and placing the bags in position to make a barrier and removal of the same after completion of work. Also the water is to be pumped out from the enclosed area , to be kept dry for working by pumping out the water as and when required. The area is to be kept without water till completion of the work in all respects up to the plinth level complete as per direction of E.I.C.	1.0	Job		

Executive Engineer(Civil),
BSNL Civil Division-II, Bhubaneswar

PART – C (ELECTRICAL WORK COMPONENT)

PROFORMA OF SCHEDULES

(operative Schedules to be supplied separately to each of the intending tenderer)

SCHEDULE “A”

Schedule of Quantities: Appended

SCHEDULE “B”

Schedule of Materials to be issued to the contractor

S. No.	Description of Item	Quantity	Rates in figures & words at which the materials will be charged from the contractor	Place of issue
1	2	3	4	5
NIL				

SCHEDULE “C”

Tools and Plants to be hired to the contractor

S. No.	Description of Item	Hire charges per day	Place of issue
1	2	3	4
NIL			

SCHEDULE “D”

Extra schedule for specific requirements/documents for the work If any.

1. Eligibility conditions for Electrical sub-head in respect of composite works (Civil & Electrical)
2. List of approved makes for Electrical works.
3. Specifications for E.I. & Fans.
4. M.V. / L.T. Panel specification.
5. Cable laying.
6. General specification.
7. Standards.
8. General Conditions.

SCHEDULE “E”

Schedule of component of Materials, Labour etc. for escalation.

NIL

SCHEDULE "F"

(Reference to General Conditions of Contract)

Name of Work: Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar - Electrical part.

Estimated cost of Work : Rs 1,58,681/- (Electrical part)

Earnest Money Not applicable

Performance Guarantee

(5 % of the tendered value in the form of Bank Guarantee from Scheduled Bank in respect of works with estimated cost put to tender exceeding Rs. 15 Lakhs)

Not applicable**Security Deposit**

(5 % of the tendered value of the Electrical part in the form of Bank Guarantee from Scheduled Bank)

Rs _____
(Rupees _____)

Officer inviting tender

Executive Engineer (Civil),
BSNL Civil Division-II, Bhubaneswar
50%

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with Clause 12.2 & 12.3

Definitions**See below**

2(v) Engineer-in charge

Executive Engineer (Elect.), BSNL
Electrical Division, Bhubaneswar

2(viii) Accepting Authority

**SUPERINTENDING ENGINEER(C)/
CHIEF ENGINEER(C)**
BSNL Civil Odisha Zone,
Bhubaneswar.

2(x) Percentage on cost of materials and labour to cover all overheads and profit

15 %

2(xi) Standard Schedule of Rates

Market rates.

9(ii) Standard BSNL Contract Form

BSNL W 7/8 form as modified upto and including correction slip No.6.

Clause 2

Authority for fixing compensation under Clause 2

**Superintending Engineer (C)/
Chief Engineer(C),**
BSNL Civil Odisha Zone,
Bhubaneswar.

Clause 2 A

Whether Clause 2A shall be applicable NO

Clause 3 A

Whether Clause 3 A shall be applicable NO

Clause 5

i) Time allowed for execution of work. To be completed along with Civil works

ii) Authority to give fair and reasonable extension of time for completion of work. [Superintending Engineer \(Civil\)/ Chief Engineer\(C\)
BSNL Civil Odisha Zone,
Bhubaneswar.](#)

Clause 6 A

Whether Clause 6A shall be applicable **YES**

Clause 7

Gross value of work to be done together with net payment / adjustment of advances for materials collected, if any, since the last such payment for being eligible to interim payment. Contract Amount of Electrical part
2xCompletion period in months.

Clause 10 C, 10 CA and 10 D

Not applicable

Clause 11

Specification to be followed for execution of work. CPWD–Electrical Specifications 2009 including up to date correction slips

Clause 12

12.2& 12.3

Limit for value of any item **50%(fifty percent)**

Clause 16

Competent authority for deciding reduced rates. Chief Engineer (Elect.)
OR
Superintending Engineer(Elect.),
BSNL Electrical Circle,
Bhubaneswar.

**ELIGIBILITY CONDITIONS FOR ELECTRICAL SUB-HEAD IN RESPECT OF
COMPOSITE WORKS (CIVIL & ELECTRICAL)**

The following eligibility conditions for electrical sub head shall form part of the NIT for composite works for engaging electrical contractor by the civil contractor.

1. BSNL enlisted contractors of Class-IV & above in Electrical category.
OR
2. The contractor satisfying the following conditions:
 - 2.1. The contractor enlisted in CPWD, MES and Railways in respective class as per their tendering limits.
AND
Average annual turnover during the last three years, ending 31st March of the previous financial year, should be at least **30% of estimated cost of Electrical part**
AND
Experience of having successfully completed similar works in Central Government/State Government /Central Govt. Autonomous Body/Central Govt. Public Sector Undertaking during last 7 years ending last day of the month previous to the one in which NIT applications are invited, should be either of the following :-
 - i. Three similar successfully completed works costing not less than the amount equal to **40% of estimated cost of Electrical part.**
OR
 - ii. Two similar successfully completed works costing not less than the amount equal to **60% of estimated cost of Electrical part**
OR
 - iii. One similar successfully completed works costing not less than the amount equal to **80% of estimated cost of Electrical part**

SCHEDULE-D (for Electrical Works)
LIST OF APPROVED MAKES OF BSNL ELECTRICAL WING

S. NO.	Item	Makes
1	Engine	Ashok Leyland/ Cummins/Cater pillar/KOEL/Volvo penta / Mahindra & Mahindra (up to 40 KVA)/ Escorts (up to 30 KVA) / Eicher (up to 20 KVA)
2	Alternator (Brushless)	Crompton Greaves (AL Series) / KEC/ Leroy Somer/Stamford / Jyoti Ltd.
3	Battery (Lead Acid / Mntc. Free)	Amara Raja / AMCO / Farukawa / Hitachi / Exide / Prestolite / Standard
4	HV Switchgear (Vacuum Circuit Breaker / SF6)	Biecco Lawrie / Crompton / Kirloskar / MEI / Jyoti Ltd
5	Transformer (Oil filled / Dry type	ABB /Schneider Electric / Andrew Yule / Bharat Bijlee / Crompton / EMCO / Kirloskar / Siemens
	a)Above 400 KVA	
	b)Up to 400 KVA	In Addition to above makes, Uttam / Automatic Electric Gear (AEG)/ Patson / Rajasthan Transformer and Switchgear
6	Air Circuit Breaker	L&T / Schneider Electric / Siemens
7	MCCB(Ics=lcu)	L&T / Schneider Electric / Siemens
8	SDF units	L&T / Schneider Electric / Siemens / HPL / Havells
9	Power Contactors	L&T / Schneider Electric / Siemens/ Lakshmi (LECS)
10	Change Over Switch	HPL / Havells/ H-H Elcon
11	Intelligent APFC Relay	L&T /EPCOS (Siemens)/ Schneider Electric /Neptune Ducati / Syntron / ABB
12	Bus Bar Trunking / Sandwiched Bus Duct	Moeller/L&T / Schneider Electric / ABB / Legrand / Zeta
13	Power Capacitors (MPP/APP)	L&T /EPCOS (Siemens) / ABB/Crompton/ Schneider Electric /Neptune Ducati
14	Digital / KWHr meter	Schneider Electric/ AE/ Digitron / IMP / Meco / Rishabh / Universal / HPL/ L&T / ABB
15	Cold Shrink HT/LT Cable Joint	Denson / 3M(M-Seal) / Raychem
16	Rubber Matting	ISI mark
17	MCB / Isolator / ELCB / RCCB / Distribution Board	Crompton / Havells / Indokopp / MDS / Legrand / L&T / Schneider Electric / Siemens / Standard / C&S / ABB / HPL
18	MS / PVC Conduit	ISI mark
19	Cable Tray	MEM / Bharti / Ratan / Slotco / Profab
20	HT/LT Cables	ISI mark
21	PVC insulated copper conductor wire	ISI mark
22	Centrifugal Pump	Amrut / BE / Beacon / Batliboi / Crompton / Jyoti / Kirloskar / KSB / Mather & Platt / Wasp / Grundfos
23	Submersible Pump	Crompton/ Amrut / BE / Calama / Kirloskar / KSB
24	Motors	ABB / Bharat Bijlee / Crompton Greaves / / Schneider Electric /

DNIT

		HBB / KEC / Siemens / Jyoti Ltd.
25	Fresh Air Fans	GE / Khaitan / Almonard / Crompton
26	Starter	ABB / BCH/ Schneider Electric / L&T/ Siemens
27	Single Phase Preventer	L&T/ Minilec /Siemens /Zero trip
28	GI/MS Pipe	ATC/ATL/BST/GSI/ITC/ITS/IIA/JST/Jindal/TTA/Tata/Zenith
29	Foot Valve	ISI mark
30	Gate Valve	Advance / Audco / Johnson Controls / Zoloto / Annapurna / Fountain / Kirloskar / Leader / Sant / Trishul
31	Compressors	Carrier / Emerson Copeland / York / Danfoss(for chillers only)
32	Resin Bonded Glass Wool	Fibre Glass / Pilkington / Up Twiga
33	Expanded Polystyrene	BASF(India)Ltd
34	Gauge	Feibig / H.Guru / Pricol
35	Controls	FLICA / Honeywell / Indfoss /Penn-Danfoss / Ranco / Ranutrol / Sporland
36	Fine Filter	Anfiltra Effluent / ARW / Athlete / Airtake / Dyna / Kirloskar / Puromatic / Purafill / Purolator / Tenacity
37	GI Sheet	HSU Jindal / National / Nippon Denro / Sail / Tata
38	Heat Detector	Appollo / Chemtron / Edward / Fenwal / Hochiki / Nitton / System Sensor / Wormald / Honeywell Essar / Notifier
39	Ionization Detector	Appollo / Cerebrus / Edward / Fenwal / Hochiki / Nitton / System Sensor / Wormald
40	Photo Electric Smoke Detector	Appollo / Cerebrus / Edward / Fenwal / Hochiki / Nitton / Wormald
41	Fire Panel (Microprocessor based)	Agni Instruments / Agni Devices / Aruna Agenices / Carmel Sensor / Ravel Elect. / Honeywell Essar / Notifier / Navin Systems
42	Sprinkler / Hose Reel & Hose Pipe	ISI mark
43	Fire Extinguisher	ISI mark
44	Lift	OTIS, Kone, Mitsubishi, Schindler, Johnson

Note :

1. In case of External /AMC works, the list of approve makes may be modified as per client's requirement.
2. The accessories such as CT / PT / measuring instrument / relays provided by approved make in respect of Transformer / HT Panel / DG / AC Package Units as supplied by approved manufacturer along with the equipments are also acceptable in addition.
3. Any additional makes may be approved by concerned PCEs/ Sr CEs/ CEs(Elect) for the work under his jurisdiction as already accorded vide letter no. 3-2-5/EW/VEP-1/2007 dated 05-07-2007..

SPECIFICATIONS FOR E.I. & FANS.

1. The work shall be done as per current C.P.W.D. specifications –1994 for electrical works and Indian Electricity Rules as amended from time to time.
2. The work shall be supervised by a qualified Engineer as provided in C.P.W.D. Manual.
3. The layout of the work will be given by the Engineer-in-charge or his duly authorized representative at site of work.
4. The following wiring shall be done on separate circuits.
 - i. Power plug wiring.
 - ii. Light & fan point wiring.
 - iii. Emergency light point wiring to be fed from battery.
 - iv. Fire detectors.
5. The earthing sets shall be provided in the presence of the Engineer-in-charge or his authorized representatives.
6. The tenderer should submit the sealed samples of materials to be used on work along with the tender .The samples of the successful tenderer will be retained by the Engineer-in-charge while the samples of other will be returned after the tender is decided Unapproved materials ,if used on the work shall have to be removed immediately at the cost and risk of the contractor.
7. The contractor will have to submit the following tests at his cost and intimate test results before final bills are paid. Nothing extra will be paid to him on this account.
 - i. Earth test.
 - ii. Polarity test.
 - iii. Insulation test.
 - iv. Earth continuity test of the conduit pipes.
8. Any damage done to the building by the contractor during the execution of work shall have to be made good at his own cost and risk. If he does not do it himself within a reasonable time determined by the Executive Engineer (E) then the same will be done at his risk by the department after giving notice to him.
9. At the time of laying conduit pipe in the slab/wall in recess the contractor will keep fish wire of 14 SWG wire throughout conduit pipe and will have to take special care so that the conduit is not passed through air-conditioning ducts, grills, columns, beams etc. If any such necessity of foreseen special written permission of Executive Engineer (E) will be obtained before such work is carried out. In case of failure the contractor will not be paid on this account. The successful tenderer should recess the conduit in the sails before they are plastered and in collaboration with the building progress of the work .Any damage done will have to be made good at the cost of the contractor .The conduit pipe should be mechanically and electrically continuous.
10. All M.S. boxes for switches plugs and regulators etc. should be provided with 3mm. thick synthetic phenolic bounded laminated sheet columns.
11. The various circuits wiring at various places shall be kept minimum by taking the runs on walls where crossing of columns is not necessary. This has to be decided before the casting of slab so that unnecessary length of conduits are not laid therein.
12. All the main distribution boards panel, sub-main board and sub-distribution boards and their complete fittings shall be sign written clearly indicating the number of

distribution board the type of load it is serving the number of circuits contained in the type of load it is serving and the number of circuits contained. In the distribution box. Details of the recess fed from the particular distribution box shall be pasted in a tabular form on the resource of the cover of distribution box.

13. Underground cables of 1 KV grade should be subjected to pressure, insulation tests before and after laying the same cost of all repairs and replacements and all extra work of removal and relaying will have to be made good by the contractor at his own cost & risk.
14. The contractor shall have to use metal clad switches and metal clad distribution of specified categories as given below unless otherwise specified.
15. Termination of all connections on main board and sub-main distribution board will be done by crimping and nothing extra will be paid on this account.
16. Inter connections on the main board and sub-main boards will be done by solid copper conductor with PVC sheathing/copper conductor cable.
17. All instruments shall be arranged by the contractor.
18. Unless otherwise specified Bakelite sheet shall be plain white colour without any pattern. Also "Anchor" or similar superior make piano switches shall be used. Both sheet as well as piano switches shall be approved by the Engineer-in-charge before execution.
19. (i) All cable having more than one strand should invariably crimped with dowells lugs/ferrules of appropriate size crimping tool is to be arranged by the contractor at no extra cost. In case contractor fails to bring crimping tools department may supply crimping tool subject to availability at an extra cost of Rs. 100/- per day per instrument. Responsibility on account of delay shall rest entirely with the contractor.
(ii) If any conduit is already laid/M.S. box is fixed in the slab/wall of the bldg. its recovery will be governed by the formula as per DSR 94 + contract abatement on the related sub-Head.
20. The piano switches for fans and light plugs shall be I.S.I. marked type/approved switches only.
21. When a boards are connected to a voltage ,higher than 250 volt all the terminals of leads of the apparatus mounted on shall be marked and the following colours to indicate the different poles or phases to which the apparatus for different terminals may have been connected.

AC .

D . C .

Three phases -

Three wire systems –

Red, Blue, Yellow

1 outer wires : Red & Blue.

Neutral :- Black

22. "BSNL reserves the right to get material inspected any components thereof by the manufacturer/ their authorized representative, whose report as regards to the genuineness of component shall be final and binding. In case any component upon such inspection is found to be duplicate/spurious, double the cost of such component based on price list (without any discount whatsoever) effective on date of aforesaid inspection shall be recoverable.

In case the contractor agrees to replace the components so found spurious/duplicate at his cost, within 15 days of the said report compensation of Rs.1,000/- per component found spurious/duplicate shall be levied against the contractor. Besides the above the BSNL reserves the right to take disciplinary action against the contractor.

Cable Laying:-

1. Underground cables of 1.1 KV grade should be subjected to pressure, insulation tests before and after laying the same cost of all repairs and replacements and all extra work of removal and relaying will have to be made good by the contractor at his own cost & risk.
2. The contractor shall have to use metal clad switches and metal clad distribution of specified categories as given below unless otherwise specified.
3. Termination of all connections on main board and sub-main distribution board will be done by crimping and nothing extra will be paid on this account.
4. Inter connections on the main board and sub-main boards will be done by solid copper conductor with PVC sheathing/copper conductor cable.
5. All instruments shall be arranged by the contractor.
- 6 (i) All cable having more than one strand should invariably crimped with lugs/ferrules of appropriate size crimping tool is to be arranged by the contractor at no extra cost .In case contractor fails to bring crimping tools department may supply crimping tool subject to availability at an extra cost of Rs. 100/- per day per instrument. Responsibility on account of delay shall rest entirely with the contractor.
7. "BSNL reserves the right to get material inspected any components thereof by the manufacturer/ their authorized representative, whose report as regards to the genuineness of component shall be final and binding. In case any component upon such inspection is found to be duplicate/spurious, double the cost of such component based on price list (without any discount whatsoever) effective on date of aforesaid inspection shall be recoverable. In case the contractor agrees to replace the components so found spurious/duplicate at his cost, within 15 days of the said report compensation of Rs.1,000/- per component found spurious / duplicate shall be levied against the contractor. Besides the above the BSNL reserves the right to take disciplinary action against the contractor.
8. Size of wire cable used for interconnection should not be less than as follows

S.No	Switches.	Alu.Condr. Size Sq	Copper cond. Size Sq.mr	Remarks
1	5	1.5	1.5	
2	10	4	4	
3	16	10	6	
4	20	16	10	
5	32	23	16	
6	63	70	25	
7	100	185	70	
8	200	300	120	
9	320	300	240	

The make specified in the item only should be supplied. However, if the same make is not available the other equivalent make will be accepted subject to corresponding deduction as per current list price. The decision of Engineer-in-charge shall be final about the equivalent make as well as the cost. However, no additional rate shall be paid, if the list price of the equivalent make is more than specified make.

STANDARDS

The design, manufacture and testing of various equipments covered by this specification shall comply with the latest issue of following IS standards:-

- a. IS 4237 : General requirements for switchgear and control gear for voltage not exceeding 1000 volts.
- b. IS 4047 : Specification for hereby duty air break switch bus and composite units for air break switches and fuses for voltage not exceeding 1000 volts.
- c. IS 2208 : Specification for HRC fuses cartridge fuse links up to 650 volts.
- d. IS 2705 : Specification for current transformer.
(Part-I to IV)
- e. IS 1248 ; Specification for direct action electrical indicating instruments.
- f. IS 2516 : (Part-I/Section-I) specification for alternating current circuit breakers.
- g. IS 375 : Switch gear bus-bar, main connections and auxiliary wiring, making and arrangements for.
- h. IS 3231 : Electrical Relays for power system protection.
- i. IS 5082 : Wrought aluminum and aluminum alloy bars rods, tubes and section for electrical purposes.

SCHEDULE -A (for Electrical work)

Name of Work:- Construction of BOV Shed in the low lying area behind the existing staff qtrs with pile foundation and RCC framed structure at Biological Park, Nandan Kanan, Bhubaneswar.					
I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	Sub-Head-I(wiring)	-			
1	Wiring for light point/fan point/exhaust fan/Call bell point with 1.5 Sq.mm. FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit,with modular switch, Modular plate ,suitable size G.I. box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc as required. (Group-C)	12	One Point		
2	Wiring for power plug with following size FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit as required.				
	a) 2 x 4 Sq.mm.with 1 No. 4 sqmm. FRLS PVC insulated copper cond. Single core cable for loop earthing.	25	One Metre.		
	b) 4 x 4 Sq.mm.with 2 No. 4 sqmm. FRLS PVC insulated copper cond. Single core cable for loop earthing.	20	One Metre.		
3	Wiring for circuit /submain alongwith earth wire with the following sizes FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit as required.				
	a) 2 x 1.5 Sq.mm.+1 x 1.5 Sq.mm. earth wire	30	One Metre.		
	b) 2 x 2.5 Sq.mm.+1 x 2.5 Sq.mm. earth wire	20	One Metre.		
	c) 4 x 2.5 Sq.mm.+2 x 2.5 Sq.mm. earth wire	10	One Metre.		
	d) 2 x 6 Sq.mm.+1 x 6 Sq.mm. earth wire	80	One Metre.		
4	Supplying and fixing the following sizes of medium class PVC conduit along with accessories in surface/recess including painting in case of surface conduit or cutting the wall and making good the same in case of recessed conduit as required		.		

DNIT

I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	a) 20mm	30	One Metre.		
	b) 25mm	30	One Metre.		
5	supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/PVC conduit as required.				
	i) 3 x 1.5Sq.mm	15	One Metre.		
	ii) 6 x 1.5Sq.mm	15	One Metre.		
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. (For light plugs to be used in non residential buildings).	2	Each		
7	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required. (a) 01 or 2 Module (75mmX75mm)	2	Each		
	(b) 03 Module (100mmX75mm)	1	Each		
	(c) 04 Module (125mmX75mm)	1	Each		
	(d) 06 Module (200mmX75mm)	1	Each		
	(e) 08 Module (125mmX125mm)	1	Each		
	(f) 12 Module (200mmX150mm)	1	Each		
8	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (a) 5/6 amps switch	12	Each		

DNIT

I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	(b) 3 pin 5/6 amp socket outlet	3	Each		
9	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	5	Each		
	<u>Sub-Head-II(fan & fittings)</u>				
10	ITC of pre-wired, fluorecent/LED fitting of all types, complete with all accessories and tube etc. directly on ceiling/wall, including connection with 1.5 sq mm FRLS PVC insulated, copper conductor, single core cable and earthing etc.as required.	12	Each		
11	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, including providing and fixing phenolic laminated sheet cover on the fan box etc. as required.	1	Each		
12	Supplying and fixing extra conduit down rod of 10 cm length G.I. pipe 15 mm dia, heavy gauge including painting etc. as required. (Note : More than 5 cm length shall be rounded to the nearest 10 cm and 5 cm or less shall be ignored)	10	Each		
13	Supplying & fixing following modular type special luminaires including making connection etc as reqd.				
	a) wall/Ceiling mounted 20W LED type batton (1213mm) with polycarbonate housing and polycarbonate diffuser & integrated electronic driver etc as reqd. (havells,or equivalent Philips/ Bajaj model)	10	Each		
	b) SITC of 25 watts treet LED light luminaire in a IP66 housing made up die cast aluminium with reflectors & acrylic transparent cover suitable for operation on 230 volts, 50 Hz, AC supply , maintenance free system, duly wired complete associated accessories, i/c connections etc as reqd.	2	Each		
14	Supplying of 1400mm 3 blade ceiling fan suitable for operation on 230 volts 50Hz AC supply etc. as required.(Usha-NEWZEN/Equivalent model of M/s Havells/Crompton Greaves/Bajaj).	1	Each		

I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
15	Supplying of 20A metal clad industrial type plug and socket with 25A 'C' series SP MCB control, suitable for operation on 230 volts 50Hz AC supply etc. as required.	18	Each		
16	Supplying and fixing of following size MS angle/MS flat/GI sheet including cutting, welding, fabricating to required shapes and sizes, painting with two coats of primer and synthetic enamel paint, fixing on wall/floor, grouting, minor civil works etc. complete as required. (a) 35mmX35mmX5mm M.S. Angle	1	One Metre.		
	(b) 35mmX5mm MS Flat	1	One Metre.		
	(c) 25mmX25mmX3mm M.S. Angle	1	One Metre.		
	(d) 25mmX3mm MS Flat	1	One Metre.		
	(e) 16 SWG MS sheet	1	One Square Metre		
17	Providing laying and fixing following dia G.I. pipe (Medium class) in ground complete with GI fittings including trenching (75cm deep) and refilling etc as required. (a) 50 mm dia	9	One Metre.		
	SUB HEAD III (Main Panel & DB)				
18	S/F following way, surface / recess mounting, Horizontal type 415V TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of tinned copper busbar, common neutral link ,earth bar,din bar, for mounting MCBs (but without MCB and incomer) as required.				
	i) 4 way (4+12), Double door	2	Each		
19	Supplying and fixing following rating, four pole, 415 volts, Isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	i) 100 amp	2	Each		
20	Supplying & fixing of single pole blanking plate in the existing MCB DB complete etc. as required.	10	Each		

DNIT

I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	<u>Sub-Head-IV (Earthing and lightning conductor)</u>				
21	Earthing with GI earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/coke and salt as required.	3	One Set		
22	Providing and fixing 25 mm X 5 mm GI strip in 40 mm dia GI pipe from earth electrode including connection with GI nut, bolt, spring, washer excavation and re-filling etc. as required	8	One Metre.		
23	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connection etc. as required.	10	One Metre.		
24	Providing and fixing 6 SWG GI wire on surface or in recess for loop earthing alongwith existing surface/ recessedconduit/ sub maon wiring/ cable as required.	35	One Metre.		
25	Providing and fixing earth bus of 50 mm X 5 mm copper strip on surface for connections etc as required.	0.5	One Metre.		
26	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required.	6	Each		
27	Jointing copper / G.I. tape (with another copper/ G I tape, base of the finial or any other metallic object) by riveting / nut bolting/ sweating and soldering etc as required.	12	Each		
28	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required. (For horizontal run)	45	One Metre.		
29	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required. (For vertical run)	24	One Metre.		
30	Providing and fixing testing joint, made of 20 mm X 3 mm thick G.I. strip, 125 mm long, with 4 nos. of G.I. bolts, nuts, chuck nuts and spring washers etc. complete as required.	2	Each		

DNIT

I.No.	Description of Item	Quantity	Unit	Rate (Rs)	Amount (Rs)
31	Providing and fixing/laying of G.I. tape 32 mm X 6 mm from earth electrode directly in ground as required.	10	One Metre.		
32	Providing laying and fixing following dia G.I. pipe (Medium class) in ground complete with GI fittings including trenching (75cm deep) and refilling etc as required. (a) 50 mm dia	5	One Metre.		
	Sub-Head-V (cables and accessories)				
33	Supplying of following size stranded Aluminium conductor PVC insulated and PVC/XLPE sheated & armoured power cable of 1.1 KV grade as required. (Finolex/Universal/Polycab, with ISI)				
	a) 3.5 core 35 sq mm	35	One Metre.		
34	Laying of one no. PVC insulated and PVC sheated/XLPE power cable of 1.1 KV grade of following size on wall surface as required.				
	a) Upto 35 Sq. mm. (clamped with 1 mm thick shackle).	25	One Metre.		
35	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required.				
	a) Upto 35 Sq. mm.	5	One Metre.		
36	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
	a) Upto 35 Sq. mm.	5	One Metre.		
37	Supplying and making indoor end termination with brass compression gland and aluminium lugs for following size of PVC insulated and sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required.				
	a) 3.5 core, 35 Sq. mm (28mm)	4	Each		

Executive Engineer (Civil),
BSNL Civil Division-II, Bhubaneswar.